


Illinois U Library

JOURNAL

ROYAL ARCHITECTURAL INSTITUTE OF CANADA

DL.28
RONT O
MAY
951
No. 5





TRANE




You Know **TRANE!**


Behind every Trane product stands Trane engineering—a constant, continuing effort designed to keep every Trane product out in front. Whatever Trane product you specify for heating, cooling, air conditioning or air handling...you are sure that it is designed right and built right. You are sure, too, that the accurate, technical information required to assure proper selection and installation is available. You *know* Trane! Specify Trane with confidence. For information about any Trane product contact your local Trane office or write to Trane, address below.




Trane Wall-Fin Heaters




Trane Projection Heaters




Trane Unit Heaters




Trane Convactor-Radiators



Trane Climate Changers




Trane Unit Ventilators



Trane Coils



Trane Traps and Valves



Trane Fans

NEW BOOKLET



"What to look for when buying or building **YOUR NEW HOME**", contains a host of valuable architectural aids prepared by a leading Canadian architect-writer. Write for your free copy to Trane Company of Canada Limited, 4 Mowat Avenue, Toronto, Ontario.

PRODUCTS ENGINEERED, PRODUCED AND BACKED BY

TRANE COMPANY OF CANADA LIMITED
4 MOWAT AVENUE, TORONTO, ONTARIO

CANADA'S LARGEST MANUFACTURER OF EXTENDED HEAT TRANSFER SURFACE

ALL-ROUND

ACCEPTANCE



is assured with

longfibre

ROCK WOOL BATTS

There's reputation in the name, it's true. But it's the product itself that earns the all-round approval of architects, builders, inspectors and homeowners. Nearly two decades of constant improvement in the world's largest Insulation Research Centre have brought these batts to their perfection. Today, they are unequalled for insulating ability and handling efficiency.



LIGHT, YET VERY STRONG

The extra long rock wool fibres in a J-M Batt are securely felted. Even very rough handling will not affect their uniformity. When applied in walls, they stay securely in place — won't settle. Overhead work is easier because batts hold their shape.



UNIFORM—RESILIENT

Batt thickness is uniform from edge to edge. Each resilient batt is cut with precision and fits snugly between framing members. When a batt needs cutting to fit odd-shaped spaces, the cut edges still stand straight and self-conforming.

HANDLING ECONOMY—J-M Super-Felt Batts are compactly packaged for efficient shipping and handling. When package is opened, each resilient batt springs back to its original full thickness throughout. They save time on the job too, because the wool is firmly felted . . . batts can be handled with a minimum of breakage.

For the complete story of this modern achievement in Home Insulation, write for brochure HI-153c, Canadian Johns-Manville, Dept. 696, 199 Bay St., Toronto.

B--301

**Johns-Manville
Rock Wool Batts**

Interior Plywood Panelling

A Lifetime of Beauty... by Master Craftsmen



The hallmark of quality stamps every interior by K. N. Crowder and Company Limited. Through the years, it stands as a distinguished tribute to discriminating good taste.

Quality of this kind comes of experience . . . of the years that our skilled craftsmen have devoted to their trade . . . of the knowledge that leads unerringly to the selection of the finest woods for each specific job! Your assurance that the traditions of excellence established by master cabinet-makers will find expression in your building interiors is secured by the fact that **cabinet-makers, superbly skilled in their art, are employed by K. N. Crowder and Company Limited.**


The above illustration shows the office of Mr. M. Church of Church Motors, 1638 Bloor Street West, Toronto. The panelling is of 1/4-inch African-stripe mahogany, all cupboard doors are hung on Kennatrack sliding door hardware. All material was supplied, and workmanship done, by K. N. Crowder and Company Limited.

For your next job . . . specify K. N. Crowder and Company Limited, specialists in commercial, industrial and institutional plywood panelled interiors.

K.N. Crowder
& Company Limited

17 QUEEN ST. EAST, TORONTO, ONT. • PHONE PLAZA 7022

If you're planning to use ONE-PIPE STEAM
to cut installation and maintenance costs . . .



Team Up With MODINE QUIET-SEALS*



*What is a QUIET-SEAL?

"Quiet-Seal" is the trademarked name of a Modine Convector designed specifically for use on 1-pipe steam systems. Patented heating unit (above) provides fast, smooth, quiet performance at full-rated capacity. Because steam, condensate (and air, when present) all flow in one and the same direction, the basic causes of water-hammer, gurgling and spitting of air-vents are eliminated. Free and easy venting prevents air binding or water-logging . . . a cause of slow response and reduced capacity.


Many thousands of Modine Quiet-Seals now in service, prove conclusively the possibility of providing excellent 2-pipe convector performance on 1-pipe steam systems.

Quiet-Seals Improve 1-Pipe Steam Performance — By permitting superior temperature control and system balance, Quiet-Seal Convectors greatly improve 1-pipe steam performance.


Having approximately 1/17th of the metal mass and 1/20th the internal volume of an average cast iron radiator, Quiet-Seals heat up many times faster . . . and as a result . . . almost simultaneously.

With Quiet-Seals, a 1-pipe steam system can be brought up to temperature much more rapidly than with ordinary radiators. Temperature require-

ments in *all parts* of a building are quickly satisfied. Consequently—unbalanced performance, caused by excessively long heating-up periods, is avoided . . . and the difficulty of providing satisfactory temperature control is eliminated.



Damper Modulated Heat Delivery for Comfort and Economy — Personalized room temperature control by manual adjustment of convector dampers eliminates expense of valves . . . discourages wasteful over-heating. When valves are used on 1-pipe steam radiators, they must be of the "on-and-off" type which do not permit modulation of heat delivery. *Only convectors offer this important refinement in 1-pipe steam heating.*



R-1102



Free Bulletin Available — For additional information on Modine Quiet-Seal Convectors and 1-pipe steam heating, get new Bulletin 250-B. Call your Canadian representative. Or write direct to Modine Mfg. Co., Racine, Wisconsin.


SARCO, CANADA LTD.

496 Church Street, Toronto 5, Ontario
Offices: Calgary, Winnipeg, London,
Hamilton, Montreal, St. John

R. E. JOHNSTON CO. LTD.

1070 Homer Street, Vancouver
833 Yates Street, Victoria

IF IT'S FREIGHT... we're interested!




We know that freight handling needs vary over a wide range. But we also know that most needs fall into well defined patterns. Accordingly, we have developed standardized freight elevators for several specific ranges of duties, as illustrated. Further, our broad experience in the field of industrial elevating qualifies us to advise on special adaptations of standardized models—and on unusual freight handling requirements. This experience is available to everyone with a vertical transportation problem. However large—or small.

HEAVY-DUTY SERVICE

where industrial trucks are used. Power trucks make fast stops, load an elevator heavily off-balance, and add their own weight to the full 'pay load'. Otis POW-R-TRUCK elevators are built to withstand power truck punishment. Lifting capacities range from 8,000 to 20,000 lbs. As described in Bulletin BC-705.


GENERAL-DUTY SERVICE

for factories, warehouses, or garage installations. Ruggedly built. Available with Unit Multi-Voltage speed regulation and "Micro" two-way, self-leveling. Otis all-steel, vertical bi-parting doors. For large openings and intensive service, power operated doors and gates are recommended. Lifting capacities range from 2,500 to 10,000 lbs. As described in Bulletin BC-382.




LIGHT-DUTY SERVICE

where space conditions are limited. Otis SELF-SUPPORTING elevators have a self-supporting framework that permits installation in new and most existing hoistways without reinforcing the building, without adding overhead supports, and without building a penthouse. For 2 or 3 floor service. 1,500 to 2,500 lbs. lifting capacities. As described in Bulletin BC-720.



SIDEWALK SERVICE

to one or two basement landings. Simple—but safe—operation is by means of key switches at the sidewalk level and UP and DOWN buttons at lower landings. Travel is 25 fpm. Lifting capacities to 2,500 lbs. As described in Bulletin BC-382.



21 OTIS offices across Canada are always interested in working with you on all vertical transportation problems. They're ready to provide Canada-wide service, backed up by full Canadian manufacturing facilities, 24-hours-a-day. For Passenger and Freight elevators. Including cars, entrances and doors. Escalators, electric dumbwaiters. Modernization and maintenance. Otis Elevator Company Limited. Head Offices and Works: Hamilton, Ontario.



FREIGHT ELEVATORS

IT WILL NOT BURN



Asbestos will not burn and in the form of asbestos-cement siding and roofing it is fire-resistant to a high degree. Build against fire loss with Turnall asbestos-cement materials.

ILLUSTRATED—"Turnall" Trafford Tile which is time-proven around the world under many climatic conditions.

IMMEDIATE DELIVERY IN ANY QUANTITY


ATLAS ASBESTOS
C O M P A N Y L I M I T E D

A Member of the Turner & Newall Organization

MONTREAL • TORONTO • WINNIPEG • VANCOUVER

TRAFFORD TILE

Atlas "Turnall" Trafford Tile is the original tile to embrace scientific principles in the design and construction of Asbestos-cement corrugated board. Reference to the Diagram below will show that the design comprises four corrugations with intervening flats. When on the roof Atlas "Turnall" Trafford Tiles give the effect of Roman Tiling. Coupled with economy, it embodies features of design so much desired by architects and builders.



FULL CORRUGATION SIDE LAP

The next important feature is that of side overlap, which, in the case of the "Turnall" Trafford Tile, comprises one complete corrugation as shown in the Diagram, the actual formation of the corrugation ensuring closer nesting on the horizontal overlaps.



Standard lengths from 4' to 10', rising by 6" increments.

Standard width, 3'8".

Net covering width when laid, 3'4".

Cover efficiency, 89 per cent.

Thickness, 9/32".

Number of corrugations per tile, 4.

Pitch of corrugations, 1'—1-1/3".

Depth of corrugations, 2".

Purlin spacing up to 4'6".

Side or Gable Girts spacing up to 6'0".

End lap, 6".

Side lap, 4" (1 corrugation).

Actual cover of 8' tile as laid, 7'6" x 3'4"—25 sq. ft.

Weight—Approx. 3 lbs. per sq. ft., uncrated.

Weight of 100 sq. ft. of laid roofing, approx. 351.8 lbs.

118 sq. ft. of tiling covers 100 sq. ft.

ATLAS ASBESTOS

C O M P A N Y L I M I T E D

A Member of the Turner & Newall Organization

MONTREAL • TORONTO • WINNIPEG • VANCOUVER

Owners benefit
from big
fuel savings...
tenants enjoy
constant
temperatures

REASON

these apartments are heated by

DUNHAM *Vari-Vac*^{*}

DIFFERENTIAL HEATING SYSTEMS



• The builder of these five Toronto apartment blocks, J. E. Evans made a sound business investment when he had Dunham Vari-Vac Differential Heating Systems installed.

Temperatures are always maintained at desired level... never too hot or too cold. Thus regardless of varying weather conditions heat wastage is kept to a minimum, assuring greatest value from fuel. Time and time again, when old-style uncontrolled heating systems have been replaced by the Dunham Vari-Vac Differential System, savings of 25% or

higher have been realized.

Naturally, greater comfort is enjoyed by satisfied tenants.

For old or new buildings, no other system can match Dunham Vari-Vac Differential Heating for constant, all-weather comfort at low cost.

Consult your Architect or Heating Engineer or write to us for details of this ultra-modern system of heat control. C. A. DUNHAM Co. Limited, 1523 Davenport Road, Toronto, Ontario.


*Variable Vacuum

**CONVECTOR RADIATION
BASEBOARD RADIATION
UNIT HEATERS • VALVES
TRAPS • PUMPS**

Sales Offices from Coast to Coast

DUNHAM

HEATING MEANS BETTER HEATING



SKF Canadian Company Limited Building

EGLINTON AVENUE EAST, TORONTO

ARCHITECT: E. C. MILLER OF T. PRINGLE & SON LTD.

OVER 150,000 SAND LIME BRICK USED
IN THIS CONSTRUCTION

FOR STRENGTH, APPEARANCE AND ECONOMY

USE

SAND LIME BRICK

THE COOKSVILLE COMPANY LIMITED

HARBOUR BRICK COMPANY LIMITED

TORONTO BRICK COMPANY LIMITED

TORONTO


EMCO Smoothbore WROT COPPER

JET

FITTINGS



"A" EMCO SMOOTHBORE.
Wrot Copper Jet Fitting



"B" Installation of Jet Fitting in Standard
EMCO SMOOTHBORE Copper Reducing Tee.

USED in conjunction with EMCO ever-lasting copper pipe for one-pipe forced hot-water heating systems.


This cone-shaped EMCO Smoothbore Jet Fitting "A" is inserted in a standard EMCO Smoothbore WROT Copper Reducing Tee "B" and a solder joint is made. The whole assembly is placed in the main, and connected to the return from the radiator. The Jet is scientifically engineered to create a suction on the return riser which draws water out of the main through the supply riser and radiator and back down through the return riser.

Install the BEST... Install EMCO


For every HEATING installation insist on EMCO Smoothbore WROT COPPER FITTINGS . . . have same coefficient of thermal expansion as the copper piping — HOT or COLD. The smooth interior walls maintain even pressure and above all corrosion-resistant and will not rust.



Distributed by Reliable Jobbers or
Service from any EMCO Branch
. . . Write for illustrated Booklet.



You get 3 important economies from *Fenestra* Steel Windows:



LOW FIRST COST

Because of standardization of types and sizes—which allows volume production.

LOW INSTALLATION COST

Modular sizes facilitate co-ordination of windows with other wall materials—installation is quick and easy for the workman

LOW MAINTENANCE COST


Thanks to the durability of steel—precision, welded construction—engineered fittings—Fenestra Steel Windows have "built-in" hardness and rigidity that's good for life-time serviceability.

Plus...

Slender steel frames, muntins and mullions to yield more daylight per square foot of window space, while helping to carry out the flowing planes of today's architecture.

Ventilator arrangement to deliver fresh air, in con-

FOUR POPULAR *Fenestra* WINDOWS



PIVOTED WINDOWS


For industrial and commercial buildings. Strong, solid-steel sections. Weather tightness assured by double contact all around vents.



RESIDENCE CASEMENT WINDOWS

Ideal for homes and a wide range of commercial buildings. Graceful, and won't warp, stick or swell. Roto-Adjusters twirl the swing leaves open with a smooth, geared action.

There is a Fenestra Steel Window for every daylighting and ventilating need, whether you want individual units or whole walls of windows. Illustrated here are 4 basic units, capable of many variations.



COMMERCIAL PROJECTED WINDOWS

Open-out vent forms canopy over opening. Open-in vent deflects drafts, allows all-weather ventilation. Easily screened. Low maintenance.



INTERMEDIATE PROTECTED WINDOWS

Popular in schools, hospitals, commercial buildings. Open-out vent forms canopy over opening. Open-in vent deflects drafts, sheds water outside.


CANADIAN METAL WINDOW & STEEL PRODUCTS LIMITED

139 STEPHENSON AVE., TORONTO, 13

4862 WILSON AVE., MONTREAL, 29



The illustration shows the last step in the manufacture of an Armstrong Circulating Pump. Careful run-in under actual operating conditions is followed by an exacting final test which is your assurance of trouble-free operation.




ARMSTRONG HEATING PRODUCTS

**Are Precision Made
For the Heating Trade**

Our Engineering and Production Staffs do not treat the symbol "O.K." lightly. To us, it means that down through the many stages of Manufacture and Assembly of our Products, a combination of Materials, Machines and Workmanship has finally culminated in a finished Quality Product. When a Product receives our final "O.K.", you may be sure it can be counted on for Long Life and Trouble-Free Performance. Complete satisfaction for your customers is enhanced by constant refinements in design — constant checking on precision of manufacture, testing and final packaging.

S. A. ARMSTRONG LTD.
TORONTO • CANADA



**Armstrong
Circulating
Pump**


The name ARMSTRONG has become synonymous with the Precision Manufacture of Heating Products for Canada's Homes, Schools, Hospitals, Industrial Plants, Apartments, etc. On your next heating installation specify ARMSTRONG Heating Products—they're PRECISION MADE for you!



For Quick Steaming

It's

PACKAGED POWER *by*



VOLCANO AMESTEAM GENERATOR

A self-contained, packaged type oil-fired boiler, which is the last word in efficient, reliable steam generation.

... Rugged—fully automatic—easy to install—low on operating cost—80% efficiency—requires no chimney—convenient to move about. Installed by one responsible party, not many. The Volcano Amesteam Generator is thoroughly approved by C.S.A. and Provincial Authorities.

Sizes: 10 H.P. to 500 H.P. Pressures: 15 lbs. to 200 lbs. Fuel: Heavy or Light Oil.

VOLCANO PRODUCTS: Stokers Steam Generators H.R.T. Boilers Cast Iron Boilers Water Tube Boilers
Indirect Heaters Dynatherm Heat Generators Oil Burners


Ask for literature
AGENTS IN ALL PRINCIPAL CITIES

VL-50-5

VOLCANO LIMITED

743 Mountain St., Montreal, Que. UN. 1591

Privacy... Sanitation...
Cheerful Color...



in **TOILET
PARTITIONS**

by
WESTEEL
PRODUCTS

**Easy to keep immaculate
Smartly styled**

Westeel Products Toilet Partitions—Sheet Steel or Aluminum—provide a pleasing, sanitary environment. They are completely private, easy to keep clean, are impervious to moisture or vermin. Easy to install in new buildings or old, will not warp or sag, give years of maintenance-free service.

Enquiries invited.

Deliveries dependent on steel supplies

WE ALSO MAKE

Lockers, Office Partitions,
Steel and Aluminum
Windows, Hollow Metal
and Kalamein Doors
and Frames, Tote Boxes,
Skylights and Ventilators,
special sheet metal work
to detail.

Send for our
new Catalogue
today



WESTEEL PRODUCTS LIMITED

MONTREAL • TORONTO • WINNIPEG

REGINA • SASKATOON • CALGARY • EDMONTON • VANCOUVER

also sales offices at HALIFAX, QUEBEC and OTTAWA



**READY FOR
RECOMMENDATION!**

Super-Tite 2/10's

Extra Protection — NHA Approved

Brantford Super-Tites are now available in 210 lb. weight for new construction under government financed building plans. They offer the best features of the popular 180 lb. weight, plus extra strength and roof coverage — triple thickness over 45% of the roof, with no less than double thickness at any point. Recommend Super-Tite 2/10's on your next government financed job.


No matter how hard it blows, or what the wind brings — snow, sleet, ice or pelting rain — Brantford Super-Tite Slates stay put. There is not a case on record where a Super-Tite Slate once properly applied, has blown off. These building favourites have a special lock-type butt, that links each slate together in an impervious roofing armour — solid and sure. Their trim keystone design is available in a selection of solid and blended colours to suit any home owner.

Brantford Super-Tite Slates

Asphalt Shingles
Sealed-In Siding
Roll Roofings
Building Papers
Roof Coatings
Built-Up Roofings
Asphalt Mastic
Flooring
Waterproofing
Materials



"It's the covering
that counts"



Address enquiries to any of these offices:


Brantford Roofing Company Limited
Brantford, Ont. — Toronto — Montreal — Winnipeg

or: **Brantford Roofing (Maritimes) Limited**
Saint John, N.B. — Halifax, N.S.

Meeting today's low
cost housing demands
and modest budget
requirements...



TUBULAR CYLINDER LOCK SET



KEY IN KNOB

To architects and builders the Corbin name implies quality material, expert craftsmanship and outstanding design. Contact the Corbin distributor in your city for full information on this new lock set.

FEATURES:

Key-in-knob convenience.
Auxiliary latch security.
Choice of several inside knobs.
Cylinder: 5-pin tumbler — may be masterkeyed for use on doors $1\frac{3}{8}$ " to $1\frac{3}{4}$ " thickness.
Reversible for right or left hand doors opening in or out.

OPERATION:

By knobs from either side or by key when knobs are locked by inside lever.

FINISHES:

Polished Brass	Satin Chrome
Polished Bronze	Satin Bronze
Polished Chrome	Satin Brass

FAST APPLICATION

Good Buildings Deserve Good Hardware




CORBIN LOCK COMPANY OF CANADA, LIMITED
Belleville, Ontario

unique in north america

The heating and ventilation system designed for this magnificent high school is believed to be the only one of its kind in a North American school and acknowledged by leading heating engineers to be one of the finest.

An integral and important part of the installation is the Carrier Duct-Type Weathermaster System. It provides individual room control of heating, as needed, by a simple turn of a dial

Such a unit serves as a junction point for primary air supplied from a duct, induced re-circulated room air and heat provided by a steam or hot water coil. The system, therefore, combines ventilation and controlled heating in one set of apparatus.



VICTORIA
COMPOSITE
HIGH SCHOOL

Victoria Composite High School Edmonton, Alta.

Architect

MAXWELL C. DEWAR
(now Dewar & Stevenson)

General Contractors

CHRISTENSON & MACDONALD


Plumbing, Heating & Ventilating

LOCKERBIE & HOLE LTD.

Electrical Contractors

SUNLAY ELECTRIC CO.

All of Edmonton



Write for the
Carrier brochures on Duct-Type Weather-
master System. Address Carrier Engineering
Limited, 172 King St. E., Toronto, Ont.

**an excellent investment
in protection and comfort**


all-metal screens by Cresswell Pomeroy

- **Canada's Finest**
- **Custom-Built For Any Type Window**
- **Completely Soldered Corners —
Reinforced With Steel Spline**

ALL-METAL—frames made from 1" x $\frac{7}{16}$ " electro-galvanized steel screen bar. Wiring (16 mesh bronze or aluminum cloth or "Koolshade" Screen Cloth) is by a removable spline method so that frames can be easily re-wired. Finished to customer's colour specifications.



Showing
Cross Section
of Screen Bar
and
Wiring Detail



TYPES

FULL HEIGHT

- | | |
|--------------|-----------|
| (a) TOP HUNG | (c) SIDE |
| (b) TOP | PIVOTED |
| PIVOTED | (d) FIXED |

HALF HEIGHT

- | | |
|------------|----------|
| (a) SINGLE | (b) TWIN |
| SLIDING | SLIDING |


**CRESSWELL
POMEROY
LTD.**

2425 GRAND BLVD., MONTREAL, P.Q.

HALIFAX • QUEBEC CITY • TORONTO • WINNIPEG • EDMONTON • VANCOUVER

For **4 in 1** Economical Heating

"GURNEY DOMINION"



The
WINTER
AIR CONDITIONING
UNIT
that

- ★ **FILTERS**
- ★ **HEATS**
- ★ **HUMIDIFIES**
- ★ **CIRCULATES**

Here's the truly modern way to heat a modern home comfortably and economically. The new Gurney Dominion removes airborne dust and pollen from recirculated air . . . squeezes out the last degree of available heat . . . humidifies to the desired extent . . . then delivers air, fresh, healthy and warm to every corner of the home.

Humidified air is a fuel-saver . . . protects families against colds . . . keeps furniture, woodwork, walls and floors from becoming too dry.

Available in four sizes to meet the need of any average home. Die-formed heavy gauge steel cabinet is attractively finished in blue crackle baked enamel.

Made in Canada for Canadians by

GURNEY DOMINION FURNACES LIMITED

TORONTO

MONTREAL

WINNIPEG

FAMOUS FOR COMFORT ECONOMY QUALITY



This staff rest room floor gives you an idea of what can be done with Marboleum when you are working on new buildings or remodelling old ones. The floor above suggests — tactfully, but constantly — "smoke time should not exceed fifteen minutes". It also shows what can be done with motifs and insets.

TIME TESTED FOR ANY WEAR... ON ANY FLOOR... ANYWHERE

MAKE floors speak. With Marboleum or Dominion Battleship Linoleum, you can design them to display trademarks, motifs appropriate to any business, or to direct traffic... Their *economy* — through lasting beauty, resilience, low maintenance cost and ease of cleaning — has been proved by over forty years service on the floors of Canadian office buildings, schools, hospitals, stores. Write for illustrated literature. We shall be glad to co-operate with you in designing specific floors.

In tiles or by the yard... a product of

DOMINION OILCLOTH & LINOLEUM COMPANY LIMITED

Montreal

Established 1872

MARBOLEUM

BEAUTIFUL RESILIENT


TIME TESTED

FLOORS



SPECIFY M^cCLARY

for every
fuel preference
and forced air heating
requirement




*Bermuda Winter Air Conditioning
Unit for coal firing.*

MEMBER
CANADIAN CHAPTER



*Bermuda Winter Air Conditioning
Unit for gas firing.*



*Bermuda Winter Air Conditioning
Unit for oil firing.*

No matter what your client's fuel preferences, be they oil, coal or gas, there is a McClary warm air heating and winter air conditioning unit specifically designed for maximum efficiency and fuel economy.

Completely enclosed in compact streamlined cabinets, attractively finished in blue hammerloid lacquer, they combine smart modern design with rugged dependability and ease of service.

The line of McClary "Bermuda" heating units illustrated lend themselves to compact heating installations, permitting a maximum of utility and recreational space so necessary in to-day's homes.

Specifically designed for domestic use, they require little attention and embody those design features and points of quality that are typically McClary.

You can safely recommend McClary heating equipment to your clients. Avail yourself of the services of a McClary representative at the very outset and be assured of qualified counsel and immediate attention to your heating problems.

You Can Depend on McClary!



ANOTHER DEPENDABLE PRODUCT
OF
GENERAL STEEL WARES
LIMITED

The Keystone...



of good building materials

Architects, Builders and Home and Property Owners everywhere in Eastern Canada rely on the name BISCO for a wide range of Roofings and many other building materials and specialties. The experience and facilities of four widely diversified divisions contribute to all BISCO products. The combination of technical knowledge and advanced manufacturing methods serves the building industry in many ways. Ask your BISCO dealer for illustrated folders on any of these top-flight building specialties, or write our nearest office:



BISHOP ASPHALT PAPERS LIMITED

Plants at PORTNEUF STATION, P.Q., TORONTO, Ont., LONDON, Ont.

Warehouses and Branches:

QUEBEC, P.Q. • MONTREAL, P.Q. • TORONTO, Ont.
HALIFAX, N.S. • SAINT JOHN, N.B.



Circulation is vital in your boiler too

GREAT CITIES CANNOT function unless traffic is kept circulating . . . free-flowing. Circulation is the lifeblood of your boiler too; and the exclusive double-ring circulation system of the Vickers-Keeler Boiler guarantees a complete, natural cycle of circulation without baffle plates or other artificial devices . . . under heavy overloading or while loafing. Vickers-Keeler Boilers assure quicker steaming, higher efficiency and lower operating costs.

*For all steam generating problems,
consult —*

CANADIAN
VICKERS
MONTREAL LIMITED

Toronto Office: 25 King St. West



If the problem is one
of **CONTAINING** or
EXCLUDING HEAT

specify
FIBERGLAS
insulation

A Fiberglas* Insulation that exceeds all normally accepted specifications is available for every application involving temperatures up to 1000° F. In cold storage applications and on high pressure boilers . . . refrigerated or superheated steam pipes . . . there is a Fiberglas Insulation designed to do a better job. Resisting all forms of deterioration, easily installed and unchanging in its efficiency, Fiberglas Insulation claims your consideration every time you face the problem of containing or excluding heat.



A Lifetime Insulation

FIBERGLAS

is a registered trade mark which identifies exclusively products of
FIBERGLAS CANADA LIMITED


FIBERGLAS CANADA LIMITED

General Sales Office: Toronto, Ont.

Branch Offices

3735 St. James Street W., Montreal, P.Q.

810 Paris Building, Winnipeg, Man.



DOMESTIC

Free-Standing—to blend harmoniously with decorative scheme of any room—impart comfort through radiation of infra-red rays.



COMMERCIAL

Wall-Hung—in steady demand for offices, stores and public buildings. Installed clear of floor, facilitates work of cleaning staffs.

Wherever
exposed radiators are indicated

Warden King
LIMITED


CAST IRON RADIATORS

are available for your
installation in styles and sizes to meet every
architectural need

Many features contribute to the continued general popularity of these handsome and practical radiators:

- **Wide Range of Styles and Sizes**—enable you to fill all building requirements, whether standard or special.
- **Symmetrical Beauty**—Open, lacy columns are in keeping with modern decorative trends.
- **Sturdy Screw Nipple Construction**, accurately machined, assures tight joints, unit strength and ease of assembly.
- **Easy to Clean**—Open construction not only enhances air flow but facilitates cleaning.
- **Greater Heating Surface**—Advanced design, including the shape and slope of the tubes, gives greater heating surface per section—which, in turn, means more heat per unit of space occupied.

Be sure you have copies of the Warden King folder ADM-9003 "CAST IRON RADIATION". It includes complete information on Capacities and Roughing-in Dimensions.



INSTITUTIONAL

"Hospital" type on high legs for wards and rooms where cleanliness is of paramount importance.

Warden King
LIMITED

"The Grand Old Name in Heating"

Head Office and Works:

2104 Bennett Avenue, Montreal

Sales Offices:

Eastern Ontario, Quebec and Maritimes:
2104 Bennett Ave., Montreal, Que.

Central & Western Ontario Branch and Warehouse:
299 Adelaide St. W., Toronto, Ont.

Sales Representatives:

Prairie Provinces & Northwestern Ontario:
G. M. Jacob, 356 Main St., Winnipeg, Man.
British Columbia:
Ames Bros., 83 Robson St., Vancouver, B.C.

Can you build better buildings
and still conserve vital raw materials?

Yes... when you build with non-critical

BRICK and TILE!




SCHOOLS

photo by R. E. Leppert, Jr.



IN FACTORIES

photo by C. D. Hubbard



IN POWER PLANTS

photo by Hedrich-Ble

Increased defense production has created a tremendous need for conservation of critical raw materials.

Clay is *not* a critical raw material. Clay deposits are unlimited!

By designing and building essential structures with Brick and Tile you free vital raw materials for use in guns, tanks, planes...and for approved civilian use.

You help increase the nation's productive capacity and *still build better buildings!*

Brick and Tile have always been "first choice" for beauty, for durability and permanence. They have always been chosen where minimum maintenance is sought—and where maximum protection of an investment is desired.


Select Brick and Tile for industrial buildings, military and naval facilities, warehouses, power plants, schools, hospitals and other essential buildings, and help avoid construction delays due to raw material shortages.

BRICK AND TILE ENGINEERING HANDBOOK

The latest edition of the text book "Brick and Tile Engineering" available to all Registered Architects and Structural Engineers, furnished free on written request.

BRICK & TILE MANUFACTURERS ASSOCIATION
OF CANADA

57 BLOOR STREET WEST • TORONTO 5, ONTARIO



**E
F
F
E
C
T
I
V
E**

metal weatherstrip

IN WINTER

*eliminates drafts and prevents
heat loss through windows and doors*

IN SUMMER

*its cloth-to-metal contact keeps
the dust from infiltrating
inside the home*

**plain and cloth-lined
all standard shapes and widths
made with non-corrosive materials**

for comfort and economy!

ask for our catalogue.



manufactured in CANADA by

UNIQUE SASH BALANCE company Ltd.


4070 NAMUR STREET MONTREAL, QUE.

SALES OFFICES AT TORONTO, WINNIPEG AND VANCOUVER

There's a place in your plans for


DONNACONA Hardboard

beautiful, permanent, interior panellings, unify Donnacona Hardboard products. Donnacona Hardboard is good and made even better. It scores of uses in the home, office, the factory or the garage, as panelling, counter material, etc. Large panels in various sizes and thicknesses are available in natural brown and three beautiful leather finishes.



Donnacona Hardboard is easily worked . . . will not crack, splinter or warp. Ideal for either building or remodelling.

Large, standard-size panels go up fast . . . speed construction . . . cut costs.



The rich glazed finish can either be left in its natural colour or painted as easily as wood. Free, fully descriptive folder on request.



Alexander **MURRAY** & Company
LIMITED


HALIFAX • SAINT JOHN • MONTREAL • TORONTO • WINNIPEG • VANCOUVER

Division of: DOMINION TAR & CHEMICAL COMPANY LIMITED

new beauty in

illumination . . .

**new economy in
cost...installation
and maintenance**



SNO-FLAKE

This luminaire by Curtis introduces exceptional attractiveness in open louver indirect lighting with silvered bowl incandescent lamps.

As shown in this typical installation, these individual units are designed for highest efficiency in classroom lighting.

For use with 300 or 500 watt silvered bowl lamps, original light output is regained with each relamping. Curtis quality is found throughout.



• Scores of Schools across Canada are equipped with Curtis Lighting Fixtures — Incandescent and Fluorescent. Please request bulletins giving complete data.



architectural Concrete



FOR BEAUTY

PERMANENCE AND ECONOMY

Schools, hospitals, public and industrial buildings — whatever the type or size, they can be built of architectural concrete. Concrete is so versatile, so ideally adapted to modern architectural design — assuring at the same time permanence, fire safety and low over-the-years maintenance. The fact that walls and ornamental parts can be cast in one operation speeds the construction schedule. Architectural concrete is economical to begin with and it saves as it serves.

Members of our technical staff will gladly assist architects and engineers to get the maximum advantages of concrete for any project involving the use of this material. Ask for free literature on concrete construction for public buildings or industrial plants.



Port Elgin School, Port Elgin, N.B.

Architects:

C. A. Fowler & Co., Halifax, N.S.

Contractor:

Kenney Construction Co. Ltd., Truro, N.S.



CANADA CEMENT COMPANY LIMITED

CANADA CEMENT COMPANY BLDG., PHILLIPS SQUARE, MONTREAL


SALES OFFICES: QUEBEC MONTREAL TORONTO WINNIPEG CALGARY

SYLVA-CORD

Decorative Charm by the PANEL
for...

The unusual embossed pattern of Sylva-Cord combines texture and design to create a finish of distinctive charm . . . a nationwide favorite for interior and exterior applications. The pressure-moulded surface of this Douglas Fir waterproof-glue plywood specialty is hard and damage resistant . . . easy and inexpensive to paint. Specify $\frac{1}{4}$ " Sylva-Cord for interiors, $\frac{3}{8}$ " for siding and gable ends, $\frac{1}{2}$ " for combination siding and sheathing, $\frac{3}{4}$ " for cupboard doors and built-ins. "Antique" Sylva-Cord . . . factory treated to produce a mahogany toned surface that requires no paint finish . . . is available in 4' x 8' panels or packaged pre-cut squares.

*Sold by Leading Lumber Dealers
Everywhere.*



H.R. MacMillan Sales

SYLVAPLY • MONO-DOR

VANCOUVER • EDMONTON • WINNIPEG • LONDON • TORONTO • MONTREAL • QUEBEC CITY

5:08-D



FOR BEAUTY, DIGNITY AND PERFORMANCE . . . IT'S *Anaconda* BRONZE

RECENTLY completed in Montreal, the International Aviation building is the Canadian hub of world air travel. This building emphasizes the fact that traditional methods, materials and *metals* must be of proven value to find acceptance in modern construction.

For instance, Mr. G. F. Drummond, Chief Architect, Canadian National Railways and A. Faustin Limitée, sub-contractors for all Bronze work made extensive use of Anaconda Architectural Bronze extruded shapes in entrance doors, windows and trim. The five-foot letters "A-I-R-L-I-N-E-S" are of welded Red Brass. A 76 foot by 27 foot section of the two-storey ground floor wing is panelled in Brass Sheet.


Both Bronze and Red Brass were selected because of their ready workability, composition, finish and their ability to withstand the years gracefully. Anaconda American Brass Limited, Main Office and Plant: New Toronto, Ontario. Montreal Office: 939 Dominion Square Building. ANACONDA — since 1922 Headquarters in Canada for Copper and Brass.



Top Illustration: View of entrance facade. Doors were constructed in one piece of Anaconda Architectural Bronze.

Lower Illustration: For the two-storey wing exterior, pleasing decorative effect was achieved with Anaconda Brass and Bronze.

For copper and its alloys...consult **ANACONDA**



TO GET Fire Safety AT LOW COST

This ever-recurring factor in planning is familiar to every architect. A first consideration is to specify fire-safe construction materials. Those who use G.L.A. Products have satisfaction in knowing that the insulation, wallboard and plastering materials are strong, economical and resistant to fire.

These G.L.A. Products add fire-safety to any building.

GYPROC WALLBOARD
GYPROC WOOL INSULATION
GYPROC SHEATHING
GYPROC LATH AND PLASTERS

Plan to use them—every one a proven standby for the construction trade.

**Gypsum, Lime and Alabastine,
Canada, Limited**

VANCOUVER









CALGARY

WINNIPEG

TORONTO 5

MONTREAL 2

Only a Few of the Many Types of POWERS Control



Have You a Copy of This New **POWERS** Catalog?

It's FREE—a valuable aid in selecting the right type of thermostatic control for:

- ☐ Arm and Leg Baths ☐ Hubbard Baths
- ☐ Individual or Multiple Type Shower Baths
- ☐ Sitz Baths ☐ Continuous Flow Tubs
- ☐ Pre-natal and ☐ Infant Baths
- ☐ Receiving, Emergency and Autopsy Tables
- ☐ X-Ray Film Developing Units
- ☐ Surgeon's Washup Sinks ☐ Dishwashers
- ☐ All types of Water Heaters, Heat Exchangers,
Hot Water Line Control ☐ Fuel Oil Heaters

No other catalog contains such a wide variety of thermostatic Water Controls for every requirement in the modern hospital.
Send For Your Copy Today!

THE POWERS REGULATOR CO. OF CANADA, LTD.

Established 1891 • Offices in Chief Cities • See Your Phone Book
TORONTO, ONTARIO, 195 Spadina Avenue — MONTREAL, WESTMOUNT, QUE., 1215
Greene Ave. — WINNIPEG, MANITOBA, 206 Tribune Building — VANCOUVER, B.C.,
207 West Hastings Street — Also Calgary, Edmonton, Halifax and North Bay
(HSCA)

MAIL
TO


THE POWERS REGULATOR CO. of Canada, Ltd., 195 Spadina Ave., Toronto, Ont.
Gentlemen: Please send copy of your Catalog 300 HS on
WATER TEMPERATURE CONTROL for HOSPITALS to:

Name.....Title.....

Firm Name.....

Address.....

City.....Prov.....



If you require further information, please call us . . . our technical staff is at your disposal. Write P.O. Box 6063, Montreal; P.O. Box 2876, Winnipeg.

B.P. Asphalt Shingles are manufactured by the makers of B.P. Flortile, B.P. Insul-Board and other building products.



Because B.P. Asphalt Shingle colours encompass the entire colour spectrum, you can achieve roof distinction and give a touch of individuality to one house or a whole project.


There are warm, glowing plain shades — new vivid blends that have borrowed the master stroke of nature to reproduce natural, pleasing harmony. Not only are B.P. Asphalt Shingles first in beauty . . . they are first in quality, too . . . designed to meet the most exacting standards and available in a variety of weights and types. B.P. Asphalt Shingles are known everywhere for their fire-resisting qualities, their ability to stand up to the weather and retain their beauty for years. Make a note . . . remember to specify *B.P.* Asphalt Shingles for every sloping roof requirement.

BUILDING PRODUCTS LIMITED


ARCHITECTS • BUILDERS

... home plans are made easier


... installation savings of up to 25%



G-E Oil Furnace



The G-E Air-Wall Register blankets cold walls so they radiate heat—you can place furniture in front of this register with no draft, no uncomfortable hot blasts.



G-E Gas Furnace

ONLY C.G.E. OFFERS SUCH A COMPLETELY ENGINEERED AND CO-ORDINATED WARM AIR HEATING SYSTEM.

G-E Air-Wall Heating teams up with the time-tested, economical standard G-E Warm-air furnace, either gas or oil, giving balanced heat in all rooms and even floor-to-ceiling temperatures.

Here is a completely coordinated, completely automatic, economical package that heats, humidifies, filters and circulates.

For information on all types of home heating write to your nearest C-G-E office.

GENERAL ELECTRIC **AIR ||| WALL** OIL - HEATING - GAS

G-E Air-Wall Heating—the most important home-heating development in years—allows more flexibility in building plans. The compact, attractive G-E furnace and the small Air-Wall ducts give you more living space—less head bumping—in your basement. The inconspicuous new-design Air-Wall registers are placed above the baseboard in the outer walls, warming them so that they actually radiate heat. You get two types of heat in one—forced warm air heat plus radiant heat—giving greater comfort and savings in fuel.

51-P-8

CANADIAN GENERAL ELECTRIC COMPANY
LIMITED

HEAD OFFICE TORONTO: SALES OFFICES FROM COAST TO COAST

WELDWOOD PLYWOOD

*Offers Many Advantages in
Modern Building Construction*



- It offers a variety of beautiful decorative effects obtainable by no other building material.
- It will last as long as the building in which it is used, when properly applied.
- It is remarkably free from any tendency to warp, shrink or swell.
- It can take and hold nails, screws or rivets close to edges without splitting.
- It eliminates plastering and wallpaper costs.
- It saves in building time because there are no stoppages of carpentry work to enable water to evaporate from new plaster walls or ceilings.
- It brings in no moisture to make windows stick and doors warp.
- It may be used not only in the construction of walls and ceilings but also for bookcases, closets, wardrobes, recreation room appointments and various articles of furniture.

When planning the construction of new buildings or the modernization of old ones, consider the above advantages of WELDWOOD Plywood. Write for illustrated literature showing its many effective applications.

Headquarters for All Your Plywood Requirements



UNITED STATES PLYWOOD OF CANADA LIMITED

MIMICO — — ONTARIO

CANADA'S PRIDE —

The NEW

BRITISH AMERICAN OIL BUILDING (TORONTO)

CHOSE CANADA'S FINEST...

Architects: Page and Steele



Amtico RUBBER FLOORING


VISIT the new British American Oil Building in Toronto and you'll see the most modern business building in the Dominion. Every detail of its architecture and appointments is supremely lovely, superbly suited to its function.

Naturally, Amtico Rubber Flooring was chosen for those areas where luxurious looks must be mated with lifetime wear. In the Travel Bureau shown here, in corridors throughout the building where traffic is heaviest, Amtico Rubber Flooring was specified. Unusual design flexibility with 23 stock colors, real rubber comfort, fire-resistance and sound-deadening qualities are other good reasons for Amtico's great popularity with leading architects everywhere.

SAMPLES ON REQUEST

A free box of 4" x 4" samples of Amtico in standard 1/4" gauge and all 23 colors sent, with illustrated literature, on request. Write Dept. CA3.

AMERICAN TILE & RUBBER CO., LTD., SHERBROOKE, QUEBEC, CANADA
In United States: American Tile & Rubber Co., Trenton 2, N.J.




UNDERWRITERS APPROVED FIRE DOORS



Tin Clad, Sheet Metal — sliding, hinged or vertical. Including all necessary hardware.

OVERHEAD SECTIONAL DOORS



One hundred per cent weather tight when closed. Suitable for residences, garages, service stations, factories, etc. Standard Model No. 50, Heavy Duty, No. 100, Wood and Steel. Hand, Chain, Motor or Electronic. Also One-Piece Garage Doors.

KALAMEIN DOORS


Kalamein Doors, frames and trim. Revolving, industrial steel, special bronze entrance doors. Copper doors and access doors.




ROLLING STEEL DOORS

(Underwriters Labelled)

Rolling Steel Doors and Shutters for all types of buildings. Easy to operate, fire resistant. Manual, chain and electrically operated for industrial use.




STEEL WINDOWS



Architectural Projected, Commercial Projected, Pivoted, Underwriters Labelled, Security, Basement and Utility Windows, also Electric and Mechanical Window Operators.


STEEL ROOF DECK



Pleasing, sturdy economical roofing for warehouses, industrial plants, office buildings and alterations to existing buildings. Any standard insulation and built up roofing can be used with E.S.P. deck.

SWARTWOUT AIRMOVER

Efficient, inexpensive, for large scale ventilation, adaptable to all types of buildings and conditions — installations need never to be higher than 32 inches.



*Your invitation to enquire
for further information
on these and other E.S.P.
quality products*

CONTRACT DIVISION

EASTERN STEEL PRODUCTS

LIMITED

PRESION-TORONTO-MONTREAL



Journal

Serial No. 309, Vol. 28 No. 5 **EDITORIAL** 120

ARTICLES

Maintenance and Materials in Schools, A. Leslie Perry	121
Colour in the Classroom, W. W. Caudill and W. M. Pena	123
School Lighting, Francis G. Reed	131
The Post-War School Programme in England, John H. Bonnick	142

ILLUSTRATIONS

Vancouver Vocational Institute, Sharpe & Thompson, Berwick, Pratt, Architects	125
Lincoln Avenue School, Page & Steele, Architects	135
Mount Royal High School, Randolph C. Betts, Architect, A. Leslie Perry, Associate Architect	136
Tillsonburg District High School, S. B. Coon & Son, Architects	138
J. G. Workman Public School, Murray Brown & Elton, Architects	140
OAA Headquarters Building Competition	146

SELECTED DETAIL

Cocktail Bar for Mr & Mrs I. Sussman, Page & Steele, Architects	149
---	-----

NEWS FROM THE INSTITUTE 150

The Institute does not hold itself responsible
for the opinions expressed by contributors

ROYAL ARCHITECTURAL INSTITUTE OF CANADA

EDITORIAL BOARD

ARTHUR H. EADIE, CHAIRMAN

ERIC R. ARTHUR (F) EDITOR

Langton Baker, Toronto; H. K. Black, Regina; F. Bruce Brown, Toronto; H. F. Brown, Toronto;
C. S. Burgess (F), Edmonton; Howard D. Chapman, Toronto; G. W. Cummings, St John's;
Gladstone Evans, Toronto; Robert C. Fairfield, Toronto; Leslie R. Fairn (F), Wolfville; George
Gibson, Toronto; Arthur Keith, Toronto; Fred S. Lasserre, Vancouver; Norman H. McMurrich,
Toronto; Earle C. Morgan, Toronto; H. Claire Mott (F), Saint John; Jas A. Murray, Toronto;
H. E. Murton, Hamilton; Forsey Page (F), Toronto; John A. Russell (F), Winnipeg; Wilson A. Salter,
St Catharines; E. J. Turcotte, Montreal; G. Everett Wilson, Toronto

J. F. SULLIVAN, PUBLISHER

EDITORIAL AND ADVERTISING OFFICES, 57 QUEEN STREET WEST, TORONTO 1

Toronto May 1951

Secretary to Editorial Board, Mrs Vera Williams

EDITORIAL

LAST NIGHT we attended a meeting of the Toronto Chapter of the Ontario Association of Architects, and we could not help thinking on the never changing problems of the profession.

Each generation has its young men demanding action, and its old men giving them their blessing. For the old men of the Toronto Chapter, this was where they "came in" twenty or forty years ago. So unchanging are the problems that we could anticipate them without looking at the agenda. Only one was missing in 1951, and that was the need for action in regard to plans for small houses. On the whole, we were far from being a youthful group, and that may account for the omission of the small house. The impact of the veteran graduates is not yet felt, but when it is, we shall see the small house plan high on the agenda — as it was in 1920, and, for all we know, in 1910 and 1890. So far as we are concerned, the support and vitality of the veteran graduate cannot come too quickly in the small house field. We have a feeling of personal guilt in the matter because the urgent need for a solution was dropped in our lap by no less a person than the President of the RAIC. At the moment, we sit baffled by this most frustrating and important of problems. In 1920, we would have made the prediction, without fear of contradiction, that, in thirty year's time, the problem would have been taken from our hands and conscience by technology — that prefabrication or a mould would produce cottages at a price that only the very poor could not afford to pay. We would have been entirely wrong.

However baffling the problem may be, we cannot avoid it or shirk it. We may launch plans for greenbelts, for city hall squares and noble vistas, we may write Pharisaical letters about our treatment of D. P. architects, but all are but a smoke screen for the real problem, the small house brat on our doorstep. Once upon a time, it would appear that all we needed were plans of great ingenuity which mass building would put within the budget of the white collar worker. Inflation proved that to be a fallacy. The plans are there, but the house itself is a will o' the wisp for the financial group we have in mind.

The solution now may lie only in a concerted effort in which architects, the National Research Foundation and the building industry join. We should like to think that, even at this late date, the initiative will come from the architectural profession. We are all thinking today in terms of publicity, and much paper is being employed to emphasize the value of the services of doctor or architect. A million dollars so spent could not compete with the simple statement of the Law Society of Upper Canada that it had put into effect a plan for giving free legal advice to the poor of Ontario. As architects, we lack the resources of the Law Society, and our particular services involve payments to others in time and material that are costly to the architect.

In the architectural profession, we too have a body of men keenly sensible of the responsibilities that go with the "protection" of a profession, and eager to play a part that will contribute to the betterment of several million of their countrymen. The challenge of the small house has not been taken up.

MAINTENANCE AND MATERIALS IN SCHOOLS

THIS IS A subject that is of great interest in these days of high building costs as every Architect knows that it is fairly simple to pick out materials that are easy to maintain but generally these are relatively expensive. It therefore is our job to weigh the merits of high first cost, interest and amortization against annual maintenance costs. This may not appear too important because in most Provinces the Government gives a grant of 50 per cent of the building cost, the remainder being paid for by bonds which must be amortized in about forty years. Excessive first cost therefore can result in higher annual charges to the taxpayers than the additional maintenance cost accompanying less costly materials. Architects with experience in school design have done this to varying degrees so my observations may be open to discussion but I have found the following suggestions to work out very well.

Considering first the exterior of a school structure, it is immediately apparent that we architects have streamlined our façades so that costly gothic exteriors and elaborate Georgian doorways are a thing of the past. Obviously these features had high maintenance costs with frequent repointing and expensive painting work. Our profession deserves a great deal of credit from the public for the realistic way that we have countered high building costs at the expense of our inclinations.

The main wall material is still brick and here we can help the taxpayers pocket book by using local bricks, usually red. Having decided on brick, mortar must be considered and for Eastern Canada a non-shrink mortar with joints well filled is essential. Parapets, if any, should have a real bond, like English or Flemish. These walls must be completely covered on the roof side and on top with metal flashing which must be anchored down to resist hurricanes as Canada has become a "high-wind" zone. Neglect of this has been costly to more than one school board. How we are going to get bricklayers to fill their joints is another matter!

Naturally we must keep down the amount of woodwork to reduce painting costs and glass blocks are an effective answer. When used the exterior joints should be painted as these often leak and damage results to plaster and paint. Glass bricks are commonly used for the top four-fifths of classroom windows but this will be found expensive compared to wood. A warning should be given that their use results in excessive temperatures in the classrooms from the build up due to the sun on the blocks. Artificial ventilation to neutralize this, requires at least five air changes

and is costly; open windows provide this easily "for free." Mechanical systems of ventilating, unless doing the heating, are therefore hardly justified, certainly not from any improvement in the health of the children.

Exterior woodwork if treated with a primer making use of the principle of "Osmosis" will not rot at the sills and will prolong the life of the paint. Dipping in this primer can be done by the large millworkers. This is important and not expensive.

Maintenance and materials regarding roofs is simplified as all new schools have flat or semi-flat roofs. Nevertheless there is one point that should be avoided in cold climates and that is: too much insulation and roofs that hold water. The combination of the two permits of a heavy formation of ice which adheres to the roof covering and as the ice expands and contracts, the felt is pulled apart or buckled, resulting in leaks and expensive repairs.

The chief maintenance concern of school board is the interior finish. The care of these interior surfaces has been thoroughly studied by the *National Committee for School Health Research* and a copy of their *MANUAL No 5* for caretakers should be in every school building. This book makes it evident that the architect can assist by specifying materials which require the minimum up keep and so reduce the daily cleaning routine.

The obvious part of a building requires the most attention is the floor, and with the advent of movable furniture it is now possible to provide covering that greatly speed up the janitor's work and at the same time improves the health of the students. It is a recognized fact that germs are carried and nourished by dust so this should be kept in mind when designing. As dust settles unless disturbed, it is obvious that a floor should have as few crevices as possible. Wood floors are therefore the worst. A homogeneous material like linoleum is the best. Rubber tile is good but expensive. Asphalt tile is inexpensive but is slippery and will crack if there are any unevennesses in the floor. There is a new asphalt tile that is resilient and will not crack but unfortunately its extra cost is considerable. Ordinary asphalt tile for schools should be three-sixteenths of an inch thick. Some schools use terrazzo for corridors and this material is easy to maintain and wears indefinitely. It is noisy but with sound absorbing ceilings this is not objectionable. Waxing is not necessary if water wax is added in small quantities to the water used for washing.

The gym floor is perhaps the most troublesome item, a hardwood floor has so much sentiment connected with it

that its use is still general. In a building where there is space below the floor a steel joist construction with two and a half inches of concrete gives a springy effect without the high cost of floating floors on springs etc. This can be covered with wood block units bedded in mastic at less cost than sleepers fill and underfloor. A good lacquer rubbed is the best surface. Where the room is a multiple use affair flexible asphalt is hard to beat. If funds are available this tile can be laid on one inch of asphalt instead of cement finish giving more resilience. One of the heavy maintenance costs of annually repainting playing lines can be eliminated by inlaying these using asphalt strips. Such a floor can be used at all times without fear of damaging the surface as with wood. It will stand washing and rewaxing at will. While it is less resilient for basketball the children soon get accustomed to the surface and schools who have had such floors for years are quite happy about them.

In multi-floor schools staircases are important. Examination of old schools demonstrates that steps of slate or marble wear badly. Metal treads are noisy and dangerous. There seems to be a good case for cast-in-place terrazzo with rounded corners with non slip tile nosings or inset strips. Such staircases are the least expensive, are easy to clean, wear well and are not dangerous. The handrails if of iron are expensive, are difficult to clean and are hazardous. A solid wall with handrails bolted through is a device that has none of these objections.

Wall treatment is the greatest item in annual maintenance. As light reflection is important light colours are a must. If this is accomplished with smooth plaster and flat paint the walls are covered with finger marks in a few weeks. Frequent washing is thus required and the paint is soon removed requiring repainting. Obviously a semi-gloss is a more substantial surface. The texture is the most important factor in keeping down painting work and it has been proved that sand-finish walls will cut painting repairs at best in half. At the same time children will not draw on such surfaces. There also seems less tendency to touch the walls and if hands are placed on the walls no marks result. One of the most common materials used in the United States for walls where there is heavy traffic is American glazed wall units. In this country such surfaces cost so much more than sand finish well painted cement plaster that it is cheaper to repaint every seven years or so than pay the interest and amortization of the added first cost.

In washrooms the same arguments apply but here consideration must be given to the fact that liquid soap will bleach most paints in one year. It is good business to spend the money for glazed tile behind all washbasins. If rubber base enamel can be secured this will resist the action of strong alkalies and provide an inexpensive surface.

The gym walls are a large area that is effectively covered with brick or structural glazed block. Generally, contractors do not like this type of construction because it means bringing a finished trade into the building during the rough construction stage with resulting high costs. The remarks therefore about sand finish cement plaster naturally apply to gym walls and with attractive colour schemes using medium dark dades a good looking, in-

expensive interior can be achieved. Basket balls will not mark such walls if a gloss enamel is used. The use of brick seems to give school interiors an institution look and when soiled they are almost impossible to clean.

Ceilings present little problem whether plain or sound absorbing. An economy can be effected in classrooms by using a sound absorbing material for pin-up space such as a half inch thick fireboard. This will reduce revibration so that plain plaster can be used for ceilings. For gym ceilings acoustic tile requires a solid backing.

Trim repainting can be reduced to a minimum by the use of other materials than wood. For instance a four inch rubber base will cost little more than wood, requires no painting or maintenance and will not be damaged from polishing machines. Asphalt base should be avoided as it is brittle. There is no dusting or maintenance of any kind. Door frames of metal are comparable in cost with wood and will not deteriorate with age. Paint will last on these indefinitely. Chalkboard trim can be made of aluminum but the added cost does not justify the use of this material as far as Canada is concerned.

Doors are now universally made of plywood so the finish is the only item for discussion. Not too light a glazing, stain with a sealer or binder and a wax finish is a life time job.

Where glass might get broken such as corridor partitions and panes in entrance doors it is an economy to specify unbreakable glass. This costs about the same as polished wired, looks better and is more serviceable.

Perhaps the greatest economy of maintenance is in the elimination of radiators. This can be accomplished by the use of forced warm air or by radiant heating. With the former, filters must be used to keep down dust and as these would require changing or cleaning once a month in a large city, the cost is considerable. Generally there is no initial saving in comparison with hot water heating. Radiant heating, however, costs at least no more, sometimes less than forced hot air or hot water with radiators and has no expensive filter problem. Both of these greatly lessen the janitors work as radiators are a headache to clean. If this is not done they provide a perfect place for germs to hibernate and when the heat goes on they take off sending a large number of the children home with sickness. There is a marked reduction in the soiling of walls due to air currents.

If a hot water system is used consideration should be given to the question of ease of cleaning radiators as already mentioned. Some radiators are very difficult, particularly cast iron connection type. Radiators permitting cleaning with vacuum cleaners without removing fronts are recommended.

Lighting fixtures can be selected that will cause trouble. Inverted bowl — "fly catchers" — are the worst, and flush concealed — "open bottom" the best. The new concentric ring, reflector base lamp units are the cheapest unit available and they give an excellent light. As these are incandescent lights the maintenance is much less than with fluorescent and more than offsets the extra power cost.

There are many more items naturally that could be mentioned but these are a few that have come to mind that is hoped have proved of interest and perhaps benefit.

COLOUR IN THE CLASSROOM

IMAGINE YOURSELF waking up one morning to find that during your night's sleep you had lost your "colour vision" — your ability to determine the colour of any object, and to distinguish the differences in colour between one object and another! Imagine the drabness of your surroundings — the depression of spirits which would be likely to accompany life in an environment of blacks and whites only, of light and darkness, devoid of all the fullness and richness which colour imparts to our daily living!

More and more our modern life makes use of colour. In our homes and business houses, in our shops and cocktail bars, in our clothes and accessories, in our automobiles, in our various media of entertainment — in fact, in all phases of living, colour predominates. Today the science of colour harmony has, with other sciences, moved beyond the limits of the merely physical and embodies, in part at least, many elements of the psychological. Today the depressing drabness of off-browns, dull grays, leaden blues would not be tolerated in a housewife's kitchen or in a modern factory's shipping room. Today both business establishments and homes are scientifically "colour-engineered" to insure a maximum of physical and psychological well-being for their inhabitants. Yet the colour-environment of our school buildings — the environment to which we intrust our children during much of their most vital phases of development is all too often neglected.

In considering the effect of colour on the well-being of the school child, let us first consider the question: What is colour? The answer, although obvious, contains many important implications for school builders and planners. Colour is a *sensation*, similar in nature to smell, or sound. Light falls upon chemical substances such as paints, or objects such as leaves or tree trunks. These objects, in turn, are so constituted as to reflect some light rays and to absorb others. The reflected light is thus bounced or "refracted" onto the eye of the human being. Optic nerve centers are stimulated; a neuron transfer is made; and the brain "registers" the existence of the sensation which we call "colour" in terms of such definable specifics as "red," "green," "yellow," or "blue."

But colour is more than merely a sensation. It is a sensation which produces certain specific and measureable results. Just as the taste (or smell) of certain substances may cause the human being to experience pleasure, or to experience repulsion, so the sensation of colour may create feelings of pleasantness and harmony, of drabness and depression, or of stimulation and excitability. It is just

this factor which causes colour to be of such importance in the classroom, for the classroom is the home — the environment — of the learning process. And when the atmosphere surrounding the learning process is harmonious and attractive, then the entire process itself is stimulated and aided. Conversely, dull and dispiriting surroundings of necessity hinder, and sometimes manage almost completely to destroy, the interest and enjoyment of the learner.

And it is the learner — the child — who is of primary importance in the classroom. The good school building is child-centered, designed to provide the most effective environment possible for the educational processes which go on in it, and to serve as a living aid to the processes — actually, a tool for learning. In both of these functions, colour must of necessity play an important part.

For children *like* colour! Far more than adults, children are colour-conscious. Consider the reaction of the tiniest of babies to gaily-coloured objects. Consider the favourite illustrations in your child's fairy-tale book, or in the books and magazines of your childhood — by far the majority of them employed rich, bold colouring. Toy manufacturers have demonstrated clearly the sale value of "warmly" coloured playthings — red, orange, and yellow balloons; red fire engines and sleighs and model automobiles and airplanes; bright yellow water toys; vivid orange-on-black bicycles. All through the child's growing years, colour plays a vital part — and in the classroom the colour should be engineered in a planned and orderly manner, to insure the happiness of the child, and to motivate him to positive reactions to the whole educational programme.

From the psychological standpoint, the colour engineer or the architect, in planning for the best use of colour in the school plant, must consider each area of the school building separately, as well as seeking to produce an attractive and harmonious whole. He must realize the fact that different functions of education are carried on in different areas, that different age-levels of children are housed and taught in different areas — and that no single colour scheme is desirable for all. Rich, warm colours tend to stimulate relatively strong reactions of the nerves, and hence lend themselves to areas designated for activities and recreations. Blues, greens, and aquamarines, on the other hand — the "cooler" colours — are more effective where contemplative effort is the order of the day. Bright reds and oranges appear to have the effect of "sharpening" perceptions, and are frequently useful along stairwells and

corridors, and as safety factors in certain shop areas and laboratory areas. Harsh or glaring tones, or exotic combinations of colours, should be avoided in the schoolroom, however. For the chief overall value of colour in the educational process is to provide an environment which brings about a general mood of acceptance and enjoyment of the classroom situation.

For this purpose, the skilful use of colour has proved most effective. In schools that have used properly balanced colour and light schemes as contrasted to traditional situation, observers have noticed more alertness on the part of pupils, more teacher enthusiasm, less teacher fatigue at the end of the day, and more pride in the building on the part of pupils and staff, resulting in greater cleanliness and care. In the modern classroom, intelligent use of colour is essential for the prevention of an institution-like atmosphere which is the result of a monochromatic colour scheme.

Of course, care must be exercised in the selection of colours for school-building interiors, in order that proper lighting effects be secured. Lighting of desirable quality and quantity is a major tool of the educational process — and in selecting colours for the classroom, attention must be given to the sources and intensity of light, to the maintenance of appropriate brightness-differences, to special uses of specified colours for deliberately planned light variations. Colour properly employed renders important services in improving the quality of light, especially in the maintenance of appropriate brightness-difference. By studying light-reflecting values of various colour tones, the architect may select colours which will promote a maximum visual comfort for the children as well as provide a pleasing schoolroom atmosphere.

Proper colour for any given school area will depend in large part on the use of the area, and on the amount and kind of light cast upon it. Different types of light will impart different qualities to the same colour. Hence the problem of whether the school area is planned for the use primarily of daylight (with maximum or minimum of sunlight), incandescent light, or fluorescent light is of importance in considering possible colour combinations. And similarly, light qualities needed for contemplative activities such as study or drafting are not the same as those desired in areas in which more active learning processes, less demanding of acuity of vision, take place. Hence light blue-green and medium blue-green tones which, in areas using incandescent or fluorescent light, might provide satisfactory and attractive light qualities for study, would not be recommended for a music room or play area exposed primarily to daylight.

Whatever the colour combinations finally selected by the classroom designer, a final check on both quantity and quality of light should always be made before the colours are actually put into use. Several excellent books on these subjects are available, and in brief the agreed recommendations as to reflective factors required from classroom walls and ceilings call for reflection from ceilings to be approximately 80 to 85 per cent, from side walls approximately 60 per cent, and from wainscot trim and baseboard 40 to 60 per cent. Naturally there are

variances allowable according to the need for sharp perception and other factors.

Perhaps more important than sheer quantity is the quality of the light reflected by the colours employed. Certainly for the younger children it is good general practice to use full, rich colours, even though some slight variance from commonly accepted standards of reflective value may result. Harmony of colour tone, too, tends to increase the value of light quality by eliminating sharp brightness-differences. Most of us can remember only too well the constant annoyance to our eyes created by old-fashioned classroom interiors in which a dark wood trim invariably appeared in direct association with white or ivory wall colours, and a harsh, glazed, glare-producing blackboard arrangement made us miserable for the large part of the day.

Today, classroom designers take more thought for the function of colour. Softer finished, high-visibility, relaxing greens may be used in blackboard construction. Warm oranges or yellows may be predominant in basement rooms such as shops. Ivory and tan combinations are found to provide excellent light-reflective values in laboratory areas, corridors, and stairwells. Peach and terra cotta blends are found stimulating and warm, and are in very satisfactory use in recreational rooms, lunch rooms, music rooms, and elementary and kindergarten-level classrooms. The architect of today keeps before him constantly the fact that *he is designing for children and for children's functions in the learning process*. And he attempts to select colours which will serve both the ends of providing proper light reflection and quality and of assuring psychologically pleasing surroundings.

Also the more thoughtful architect-designer makes use of materials which are at once structural and colourful. Too many so-called "experts" on colour presuppose that the colours will of necessity come in cans of paint to be applied to walls and ceiling, floor and trim of the classroom. Often they take the position that walls and ceiling must be constructed of materials which *must* be painted, such as plaster. Yet it is obvious that the classroom allows for the use of many desirable structural materials such as brick, natural woods, plywoods, glass, or tile — all of which have their own colouring, and may hence serve both colour and structural functions.

The problem of colour in the classroom, then, involves far more than merely "picking out" one colour or another to paint walls or ceiling with. It involves a thorough study of the educational processes to be carried on within the given classroom area. It involves consideration primarily of the children themselves, of their age-levels, their activities, their classroom equipment and decorations. It involves appreciation for structural materials available to provide desirable colour variations. It involves knowledge of the fields of colour harmony, light and colour, colour psychology, balance and design. All these abilities the architect-designer must bring into play in creating in today's classroom an atmosphere which will truly further the well-being of the child and stimulate in him a liking for and a receptivity to the learning process.



N. ELEVATION

VANCOUVER VOCATIONAL INSTITUTE, VANCOUVER, B.C.

SHARP & THOMPSON, BERWICK, PRATT, ARCHITECTS

Victor Thorson, Structural Engineer

D. W. Thomson, Mechanical Engineer

A. E. Simpson, Electrical Engineer

Commonwealth Construction Co. Ltd, General Contractors




MAIN ENTRANCE ELEVATION.

COVER

STAIR TO
NAVIGATION
BRIDGE

PETER VARLEY




GROUND FLOOR

- 1. & 2. Entrance Lobbys
- 3. Administration
- 4. Machine Shop
- 5. Boiler Room
- 6. Electrical Rooms
- 7. Storage
- 8. Locker Rooms
- 9. Receiving Elevator
- 10. Parking Court
- 11. Barber Shop
- 12. Woodworking
- 13. Motor Mechanic Shops
- 14. Diesel and Steam Shops


1. Chemistry and Physics Labs.
2. Welding Shops
3. Plumbing
4. Refrigeration
5. Motor Mechanics Classrooms
6. Electrical Shops
7. Building Services
8. Shoe Repair

1st FLOOR




1. Classrooms
2. Dining Room
3. Training Kitchens
4. Cafeteria
5. Watch Repair
6. Office Practice
7. Home Economics
8. Nursing Wards

2nd FLOOR



1. Navigation and Radar Classrooms

3rd FLOOR




STAIR TO NAVIGATION BRIDGE





PETER VARLEY

MAIN ENTRANCE STAIR



VIEW OF INNER COURT FROM UNDER GALLERY





GRAHAM WARRINGTON

S.E. CORNER



PETER VARLEY

CONNECTING GALLERY 2nd FLOOR



PETER VARLEY

E. CORRIDOR 2nd FLOOR

SCHOOL LIGHTING

THE SCIENCE and practice of the illumination of school classrooms has been a subject for much study by school officials, their architects, and particularly their lighting engineers. The bibliography of articles and books produced within the last fifteen years is quite formidable. Extensive practical tests have been made, some independent authorities, some sponsored by commercial interests. All these have contributed substantially to the body of scientific knowledge. We now look for simple conclusions, usable data, and reasonable specifications that will ensure adequate results in the form of visual benefits in the classroom.

So far the results don't look too simple, and those who are hoping for rule-of-thumb procedures may be disappointed. We can only say that there has emerged a limited variety of practical lighting methods, both natural and artificial, and that these are each hedged with their own special restrictions depending upon the many variables that surround them. It is encouraging to know that virtually all of the researchers find themselves to be in comparative harmony, at least on fundamentals.

Before launching into a discussion of the techniques of classroom lighting by both natural and artificial means, let us look briefly at the objective — *to produce a comfortable visual environment for the relatively severe and prolonged seeing tasks of the classroom.*

OBJECTIVES

(a) Quantity

How much light is enough? There is no simple direct answer to this because seeing benefits accrue at much higher levels than may be economically attained. As the illumination level is raised from zero the eye-benefit curve rises very rapidly, then flattens out according to the law of diminishing returns. Up to 30 or 40 foot-candles the improvement under increasing illumination is quite pronounced (see Fig. 1), and it continues at a relatively lower rate well past 100 foot-candles. The recommended level of illumination therefore cannot be an optimum but rather one influenced by the practical consideration of cost. The School Lighting Committee of the Illuminating Engineering Society in 1947 proposed a minimum level of 30 foot-candles for ordinary classrooms (see Table I). This was approved in 1948 by the AIA and the American Standards Association. The Committee, incidentally, was composed of nineteen members: two architects, two consulting engineers, three university department heads, a state educa-

tion department, two board of education representatives (including one from Toronto), a sight conservation bureau, four utility engineers (including the Ontario Hydro), and four representatives of industries.

The Ontario Department of Education now recommends 20 to 30 foot-candles minimum. The general practice in applying this standard is to use the higher level for new schools and alterations to older urban schools, the lower for alterations to all small rural schools.

(b) Quality

So much for quantity. The matter of quality is another thing, and not as readily specified; yet it is a factor of utmost significance in classroom lighting. Doubtless all readers have heard this discussed under the involved title of "distribution of brightness in the visual field." Simply, the aim is to minimize brightness contrasts. Obvious brightness contrasts are recognized as "glare" and easily avoided because recognized. More subtle contrasts if persistent may also have a deleterious effect, sometimes not limited to the eyes alone but to general health and physical and mental development.

To avoid a technical discourse and yet give some usable data we may summarize the recommendations for brightness control by stating relative brightness ratios that are considered allowable in classrooms. These are set out in Table II. But what specifications will ensure these results? Obviously these: specifications relating to the brightness of window areas and luminaires, and the reflectances of ceilings, walls, chalkboards, tackboards, desk tops, and floors. Fig. 2 illustrates the recommended surface reflectances which, in combination with proper luminaires, will produce good brightness ratios. The writer believes that classroom colour schemes can be made to meet the specifications shown in Fig. 2 without seriously limiting the designer. They allow full liberty in both hue and saturation, and reasonable liberty in value.

METHODS

(a) Daylighting

In most classrooms daylight is the primary light source. It is therefore reasonable to seek a means of using it to utmost advantage. Several methods have been employed to introduce a greater quantity of daylight into the classroom. Sometimes these devices have been highly successful, sometimes of doubtful value, and sometimes an expensive disappointment. In the latter instances the fault may not be in the basic methods used, but in the manner and

circumstances in which they were employed.

Most of our ideas on this matter, and our subsequent practice, have developed out of new design concepts employed by architects in California and Texas under the inspiration of Dr Bursch (California State Division of Schoolhouse Planning) and Dr Harmon (Texas State Department of Health). These new design concepts include a variety of devices to introduce daylight into the classroom: bi-lateral lighting, light-directing glass block, roof monitors, exterior projections, interior and exterior louvres, and the like. The results achieved have been carefully investigated and tabulated. On the whole, though certainly not without exception, they were good for that




FIGURE 1

The curve summarizes the results of several investigations involving the visual recognition of test objects.

latitude and climate.

Our Canadian architects, or perhaps rather their clients, have sought to emulate these southern examples, sometimes with little regard for the altered geographical circumstances. Some of these southern classrooms have been deposited on Canadian soil with no attempt to critically




FIGURE 2

Reflection factors desirable for classroom surfaces.

analyse the conditions that made them satisfactory in their natural habitat.

We are not prepared to set down here proposals for adapting them to our use nor are we able to propose new design concepts that might adequately meet our conditions. The fact of the matter is, no engineer or architect is in a position to point the way in this regard until adequate studies have been carried out to a sufficient extent to indicate procedures likely to be fruitful. cursory field checks of quantity and quality of daylight illumination in the contemporary style of classroom have been made by the writer. The results are sufficiently good to indicate that these new designs have possibilities, and sufficiently bad to indicate that more factual data is needed for the guidance of designers.

At the request of the Ontario Department of Education, the Research Division of the Ontario Hydro is now undertaking a thorough study of this subject. The Department has indicated that it desires research in the whole field of classroom visual environment, including both daylighting and artificial lighting in classrooms of traditional and contemporary design. The project will require a year or more to complete.

In the case of the traditional style of classroom, enough is already known to indicate suitable specifications for maximum daylighting with good brightness control:

1. Prohibit the introduction of direct sunlight by orientation so that the major window area of the room faces that portion of the sky that has the most uniform light. Therefore the main windows of the classroom should face north. An eastern exposure may be used as second choice if a louvred awning or roof exterior is incorporated in the building to shade the windows from direct sunlight.
2. Windows should begin at a point three and a half feet from the floor and continue clear to the ceiling, and should extend the entire length of the room. The elimination of the blank section of the window wall at the front of the room is desirable, for its presence puts the front chalkboard in comparative darkness.

Ordinarily when windows occupy so much of the outside wall, classrooms with northern or eastern exposures have no appreciable veiling glare on the blackboard. If smaller window areas or different exposures are used so that veiling glare is present on the front chalkboard, louvering the front window to reflect the light to the ceiling will eliminate glare.

Discomfort occurs whenever intense light can enter the eye at angles below the normal line of sight. Windows three and a half feet from the floor are above the direct line of sight for a child seated, but permit him to see outside when standing.

Tests have proved that the light entering the room from the top of the window is the most effective. The inside row of desks receives 41 per cent of the illumination from the upper quarter of the window. Therefore glass should extend as close to the ceiling as possible. If the construction method will permit the elimination of practically all of the header, so much the better.

Mullions should be as narrow as possible. In warmer climates it is feasible to use steel sash and frames, and so reduce mullion space to the minimum. Where that is not feasible, other means should be used to reduce the size of glass interruptions.

3. Proper desk arrangement is a key factor in the classroom visual environment. The recommended pattern for a unilaterally lighted room is obtained by drawing a line diagonally across the room at 50° with the window wall, originating at the front of the first window. All desks in front of this line should be faced straight ahead, with the line of sight parallel to the window wall. All desks behind the line should be faced so that the line of sight makes an angle of 50° with a line drawn from each desk to the front of the first window.

(b) Artificial Lighting

According to the Ontario meteorological records 60 per

cent of all school days are "dark" days. In spite of all efforts to get daylight into the classroom there are times when its value on the desks at the right side of the room is as low as 5 foot-candles. We have made tests of classrooms employing bi-lateral lighting with clear glass and also of rooms with light-directing glass block fenestration, and in certain cases have found the light level at the inside row of desks to be less than 5 foot-candles. This was with a heavily overcast sky, but with no smoke or dust in the atmosphere.

A specification for a 30 foot-candle minimum level means of course *combined* natural and artificial illumination. The amount of natural lighting, however, is an unpredictable quantity. If we were certain to have as much as 15 foot-candles of daylight on the inside row of desks at all times then we could meet the requirements by designing a lighting system to add a further and equal amount. But we know from experience that we cannot be sure of the natural lighting. Add to this fact the possibility that some classrooms may be used at night for educational or community purposes, and the conclusion is that the artificial lighting system should be able to meet the full requirements *whenever necessary*. If the system is designed to be flexible then it will be possible to use only what is needed at any given time.

Where financial considerations prohibit a complete system it is suggested that the complete wiring be installed, with luminaires for only the dark side of the room where it is certain that night classes will not be held. To install two rows of luminaires (three units each) in a three-row system is perfectly feasible. To install one row of a two-row system, however, is inadequate; for in the first place a two-row system of six units can deliver scarcely 20 foot-candles of illumination.


Fig. 3 illustrates a few typical luminaire layouts, with details of type and resulting illumination levels noted.

Fixture or luminaire types for the classroom are subject to more restrictions regarding allowable surface brightness than are those used for most other purposes. There are three main types, the first two being incandescent (that is, filament lamps) and the third fluorescent (gaseous discharge). They are:

1. *General Diffuse*. This is enclosing glassware. Its surface brightness exceeds the recommended values for classroom lighting, but because of its low cost it is still tolerated provided it may be mounted not lower than 11 feet from the floor. Opal globes for either 300-watt or 500-watt lamps should be not less than 18 inches in diameter.
2. *Indirect*. This type uses the ceiling as a secondary light source, therefore the ceiling must have a matte white surface with a reflection factor of not less than 85 per cent, and it must be maintained so. Indirect luminaires are quickly affected in efficiency by dust, and must be kept clean constantly. The "silver-bowl" type is less affected than are other types and requires a little less maintenance.
3. *Fluorescent, Semi-Direct*. These may be open, or enclosed by diffusing glass or plastic. If open, they should be louvred or shielded so that bare lamps are not seen at normal viewing angles. They should be suspended

about 10 feet from the floor. For very low ceilings they may still be employed provided the side panels are not too bright. Where mounted low it is usually best to employ the type having all four lamps in a horizontal plane rather than in a U shape, as this minimizes side panel brightness. Louvred industrial fixtures or "trofers" may sometimes be recessed between the joists to produce very effective illumination for low-ceiling basement classrooms. Fluorescent light has no more harmful effects than any other kind and, contrary to some reports, the fluorescent powder from broken lamps is not poisonous to the skin. In rural schools where maintenance is a somewhat casual matter it is advisable to

FIGURE 3
Typical lighting plans for a classroom 23 x 32 and 12 feet high.



use instant-start lamps and ballasts, which have no starters to become defective. All lamps should be 40-watt and standard white in colour. So-called "daylight" lamps have no advantage, are lower in light output, and a little ghastly in appearance.

Chalkboard lighting is mainly justified by the fact that any general lighting system that will produce a given level of illumination on the desks will produce only half that amount on the vertical or near-vertical surface of the chalkboard. Supplementary lighting is therefore required.

The most effective system, that is the one delivering the greatest amount of illumination for the lowest power consumption, is one consisting of the reflector or projector type lamps. The equipment which holds the lamps (sockets, fittings, etc.) may be fully exposed for especially

low-cost installations, or it may be surface mounted with concealed wiring, or it may be fully recessed flush with the ceiling and concealed by louvres. Where 150-watt projector-flood or reflector-flood lamps are used they should be aimed at an angle of 25° to 27° from the vertical, spaced approximately four feet apart, and the distance from the front wall should be approximately .70 of the height from the horizontal centre of the chalkboard to the ceiling.

Other types of equipment involve the use of prismatic lens plates or silvered glass reflectors. Information about these and costs can be obtained from reputable electric equipment distributors. These units must be installed according to the manufacturers' printed instructions.

TABLE I
Lighting Levels at the Work (Maintained after Depreciation), Current Recommended Practice


LOCATIONS	Minimum Footcandles
Classrooms — on desks and chalkboards	30
Study halls, lecture rooms, art rooms, offices, libraries, shops and laboratories	30
Classrooms for partially seeing pupils and those requiring lip reading — on desks and chalkboards	50
Drafting rooms, typing rooms and sewing rooms	50
Reception rooms, gymnasiums and swimming rooms	20
Auditoriums (not for study), cafeterias, locker rooms, washrooms, corridors containing lockers, stairways	10
Open corridors and store rooms	5

In all cases it is essential to obtain units that will be rigid when installed so that they can not be put out of correct adjustment during replacement of lamps or cleaning. Ordinary clamping devices are seldom satisfactory.

The *American Standard Practice for School Lighting 1948* is a very safe guide for the lighting of classrooms by both natural and artificial means, with this reservation — that we have yet to learn more about daylighting in our latitude and climate. It is hoped that the studies currently undertaken by the Hydro's lighting research group will produce data that will be translated into reasonable specifications for the guidance of designers.

TABLE II
Recommendations for Limits of Brightness Ratios in Schoolrooms

LOCATIONS	Ratio
a. Between the "central visual field" (the seeing task) and immediately adjacent surfaces, such as between task and desk top, with the task the brighter surface	1 to 1/3
b. Between the "central visual field" (task) and more remote darker surfaces in the "surrounding visual field," such as between task and floor	1 to 1/10
c. Between the "central visual field" (task) and the more remote brighter surfaces in the "surrounding visual field," such as between task and ceiling	1 to 10
d. Between luminaires or windows and surfaces adjacent to them in the visual fields	20 to 1



MAIN ENTRANCE

LINCOLN AVENUE SCHOOL, GALT, ONTARIO


PAGE & STEELE, ARCHITECTS

Wallace, Carruthers & Associates Ltd, Structural Engineers

Karel R. Rybka, Mechanical Engineer

E. L. Dodington, Electrical Engineer

Ball Bros Ltd, General Contractors



GROUND FLOOR

FRONT ELEVATION






FRONT ELEVATION

MOUNT ROYAL HIGH SCHOOL, MOUNT ROYAL, QUEBEC

RANDOLPH C. BETTS, ARCHITECT, A. LESLIE PERRY, ASSOCIATE ARCHITECT

McDougall & Friedman, Consulting Mechanical Engineers
 Pentagon Construction Co. Ltd, General Contractors




GROUND FLOOR



MAIN ENTRANCE TOWER

1st FLOOR







FRONT ELEVATION



TILLSONBURG DISTRICT HIGH SCHOOL, TILLSONBURG

S. B. COON & SON, ARCHITECTS

The Foundation Co. of Ontario Ltd, General Contractors
 Wallace, Carruthers & Associates Ltd, Structural Engineers
 Fred Stott, Mechanical Engineer







TWO VIEWS OF PORCH



AUDITORIUM CLASS ROOM



CLASS ROOM

THE POST-WAR SCHOOL PROGRAMME IN ENGLAND

THE FOLLOWING is a portion of an original report based on a survey made this past summer on the post-war school building programme in England. Beside extensive field trips and discussions with the County Architectural offices at the City of Coventry and counties of Lancashire, Essex and Hertfordshire, considerable research was carried out at the library of the RIBA. To the many who were both encouraging and co-operative I am greatly indebted.

The problems confronting school architects in England's post-war era were essentially threefold. With the majority of existing buildings quite inadequate and below the required technical proficiency there arose a great demand for new schools. Yet, in the national picture the primary post-war construction need was for homes. Thus it was inevitable that the greater majority of building labour available would be employed in erecting houses — not schools. Another factor which aided the turn of tide came in the year 1944, when Parliament approved the New Education Act. Here, in quite detailed form, has been set the standard of requirements to be incorporated in all future schools. It was, in reality, a yardstick against which all subsequent schools have been measured. Coupled with both factors is the influence of the client — the child. As Alfred Roth so aptly puts it "the child is the focal point of all school building problems, and around him should gravitate all considerations of education, town planning and architecture."

Such, in brief were the basic problems — the solution was yet to come.

Almost immediately, the various County Architectural offices were delegated complete charge in dealing with the particular educational problems of the areas to which they served. As such, nearly all the school buildings erected in England to-day are by these groups. Where a private architect has been commissioned a building, he is usually under the direct jurisdiction of the county architect.

Once the basic administrative machinery began operating, research was immediately carried out by the various groups as to the best type of construction. The insecure material problem carried great influence in this respect. The two systems — prefabrication of units and traditional building methods were exploited, and in the majority of cases, prefabrication was the final solution. Of the four counties covered in the study tour, three employed a prefabricated structural system.

Next came the all-important factor — architectural design. For the child, the school building is the starting point

on the road to aesthetic appreciation. The importance of good design cannot be overemphasized. The British Architects are not consciously concerned with trying to create a new style in school design. Rather, their aim has been to provide buildings which, within the complex limiting factors of sites, money and material available, furnish the best equipped and arranged accommodation for current educational activities. "They have used modern structural engineering technique, contemporary materials and apparatus and the most recently formulated knowledge in science, sociology, child psychology, hygiene, planning and organization of the building. Their architecture grows out of the solution to these problems, inexorably and unalterably from the main massing and grouping down to the most trivial details. The building is an organic creation growing out of practical considerations. They have no preconceived ideas of what their buildings "ought" to look like, but select, modify and transpose the practical elements of their designs to form a pleasing and satisfying composition."*

Generally, there is a certain visual pleasantness and lightness about the work. Often a dash of elegance has been introduced. Materials like steel, aluminium and reinforced concrete, have aided in decreasing the need for heavy structural members and made possible a new sense of freedom and space. All buildings are well lighted, well ventilated. This would obviously create an admirable effect on the children. Elevations have generally been kept simple in treatment and walls are but mere protective shells, glazed or opaque as required. Flat or gently sloping roofs have largely replaced the traditional steep roofs of slate and tile.

The long, low classroom blocks, broken only by an occasional vertical emphasis of dominating mass (assembly hall, gymnasium or water tower) fit quietly into the pattern of the modern community in a neighbourly manner. Although little landscaping has as yet been executed, it is the hope that free shapes of trees and planting will help to blend the more formal lines of the building with the landscape.

Yet, the schools so far mentioned are hardly the ultimate. They are too sterile. Architecturally, they are too geometrical in concept and require more "loosening up" of the various elements. Where a brilliant effect has been achieved in one building, it has been incorporated into all subsequent designs. Thus, though the various architects

* New Schools Book issued by the RIBA.

advocate most strongly the predominance of individuality of design, the overall concepts do not always appear this way. This is, to a large extent, quite unavoidable due to the standardization of both material and structure. Here was a necessity — not a choice.

PLANNING

Judging from the schools visited, whose examples no doubt are closely followed in other parts of the country, the following are the main factors that resulted in a new trend in English Schools.

1. The admission of sunlight and standards of daylighting set for all classrooms.
2. Division of units in relationship to noises.
3. Introduction of a general purpose room where physical education may be practiced.
4. Meals are served to all children at noon hour.
5. The utilization of the assembly hall for music, theatricals and cinemas, as well as by the adult community.
6. The adoption of a module (usually 8 foot, 3 inch) in all planning.
7. Multi-purpose aspect of all classrooms.

Coupled with the above, one must realize that England was one of the first countries to realize that the one-storey school consisting of a number of loosely connected parts is much better suited to the requirements of modern education than the traditionally concentrated multi-storey school. Also, one should note that the new building regulations of 1944, especially those covering daylighting are virtually enforcing a single storey plan. All schools visited, save three (all secondary schools) were of the one floor type employing either bilateral or skylighting in every case. In all cases where two floors were adopted, intricate planning was necessary, so that both floors could enjoy cross lighting. One such solution employed in Essex, was the overhanging of the upper classroom so that the corridor was above the ground floor teaching area.

Before the daylight factors were introduced, the accepted standard was a minimum factor of 0.5 per cent. This has now been raised to a minimum of 2 per cent and a recommended percent of 5. Orientation has proven a great aid in achieving this required standard, and consequently all classroom blocks have south-east exposure. This is an accepted procedure in all schools.

With all classrooms on only one side of the corridor, the main weakness of the one-storey scheme is the great tendency to sprawl. This is evident by the fact that the relationship of actual working space to ancillary area is now 1 to 2 or even higher. This has definitely increased costs, due to relatively large areas to be heated, lengthy piping services and a high proportion of foundations and roofs. As yet, no solution has been brought forth to solve the difficulty, but as the architects feel orientation is definitely the most important factor, they are ready to sacrifice large ground areas and higher costs to achieve it.

Along with the disadvantages gained through utilizing only one side of the corridor, is the difficulty in keeping corridors to a minimum in length. At times, plan layouts were almost forced to secure an effect of short corridors. Classrooms were often jogged to create breaks — for psychological reasons. Usually this method was quite

successful, but it did tend to create unnecessary complexity out of what otherwise might be a straightforward scheme.

Most of the school building programme and certainly research so far, has concentrated on the Junior and Infants School. Space within the structure is generously divided and each group of teaching areas (usually 3 classrooms) has their own lavatory facilities as well as cloakrooms and storage spaces. The use of separate cloakrooms (not necessarily adjacent to the classrooms) is a pleasant feature that should be incorporated in all Canadian schools.

Classrooms are no longer merely a place to work, but are complex and extremely flexible in nature. They are a humdrum of activity—workshops, studios and play-spaces. The most recent innovations are to break up the room into a series of alcoves, each holding one or two small groups, reduce the scale of clerestory lighting and to utilize the corridor as an extension of the teaching space. Thus, all classroom and corridor partitions are flexible (sliding doors) and the whole has been treated as one space.

All teaching areas are planned around exterior court yards, with asphalt play areas and the necessary sand pits, paddling pools, etc., being adjacent. No longer, is there evidence of separate entrances dogmatically labelled Boys and Girls. The main entry and lobby is forceably used by parent, guest or child alike. Usually the assembly hall and dining area is linked to the foyer so that walls may be folded back and the entire area become one unit.

COLOUR

Perhaps the finest feature (certainly second only to the structural systems evolved) is the way colour has been utilized. In all cases, colour has been utilized in an "organic approach." Here, colour and form are considered inseparable. For each surface to fulfil its natural and functional condition, colour must "speak the truth" and express the designer's original intention.

There are a vast number of factors that determine the appropriate use of colour. I consider, by far, the most important factor is the children. With their bright clothes, high-pitched voices and quick movements, they create exciting patterns, whatever activity they are engaged in. Biologically, they are attracted to primary colours, and hence the schools must arouse and reflect these tendencies. Certainly the schools of the Hertfordshire group are the greatest exponents of this theory. Brilliant colour is employed both indoors and out. Generally there is a different treatment for each wall, ceiling, as well as furniture. In contrast, it is interesting to note the philosophies of the Swiss. Here, the use of colour is restrained to a small portion, be it a painting or fragment of coloured glass. Main masses are kept in neutral shades, as it is felt the children themselves create a sparkling pattern and to unnecessarily repeat such feeling into the decoration would only cause discord.

Colour also has the ability to distinguish various activities of a building. In entrance halls and circulation areas, where there is a constant movement, bold colours have been employed, and often most stimulating effects have resulted. The use of planting, together with materials of varying texture also enhance these ideals. Generally, the

entrance hall has been made the most vivid and exciting unit in the school. It is purposely made to look inviting. In assembly halls and dining rooms, where large groups converge, a more dignified approach is utilized. Bright and jolly colours are used for psychological reasons, but the treatment is limited to larger areas. Tinted acoustic tile, natural wood and curtains of unusual pattern have often been utilized to, as the Hertfordshire group states "create something more than a merely passive background — a character which will catch the imagination on entering." Teaching areas have been treated more informal and domestic in character. This is due to the multi-activity



CLASSROOM WING

Manford Way Primary School, Chigwell
Harold Conolly, Architect

these rooms are planned for and no longer is an institutional setting applicable.

Lastly, is the obvious relationship of colour toward the aesthetics of the structure. The prefabricated frame construction used by most of the schools presents a visual pattern of beams and columns with panels inserted between them. With so much of the structural system actually exposed, a discipline had to be maintained in the interiors so that a conflict between structure and wall panels would not result. Consequently, most structural members have been constantly painted a neutral shade (pale grey) in order to avoid an inappropriate decorative treatment, while the "filler" or wall panels receive colour (usually bold) appropriate to the spaces they enclose.

The aims of architectural design and colour is generally at spaciousness and gaiety, at unpretentiousness and extreme informality. Nevertheless, in many cases the solutions failed to achieve such pleasing proportions. Colour is often unnecessarily used to the degree where the whole concept glows like a brilliant paint box. The ultimate will be a more restrained and refined solution of the same problem. The tendency in most architectural offices has been for the job captain (designer of the project) to decide on the individual colour schemes. Few cases showed the consultation of a qualified interior decorator. Thus, the

schools do, to a great extent, express the character of the designer. Schools executed under one authority were found to be in some cases brilliant and gay with bold patterns, while in others, quite restrained and often unnecessarily severe. This tendency has the advantage of divorcing the schools from what otherwise might become a standardized method of treatment.

SCULPTURE

Other methods have also been employed to aid in the decorative schemes. Superimposed and changeable units of decor like curtains, planting, pictures, books and sculpture are to mention but a few.

Of particular interest is the emphasis placed on the value of sculpture and mural decoration. Local authorities generally allocate a small proportion of the total building cost for the work of sculptors or mural artists. It has been found that due to the prefabricated methods of construction, sculpture can contribute more successfully to the character of the school when it is free-standing than when it is carved into the wall surface or placed in a special niche. Usually an informal siting is adapted and the backgrounds (material, size and distance away) have been carefully considered. Generally, sculpture is of a subject appealing particularly to children, as the Kangaroo flag-stand at Canley School, Coventry. Perhaps the finest work is at the Barclay Secondary School, Stevenage where a piece executed by Henry Moore adorns the main entrance. The siting here is of particular merit. In the cases where sculpture has been carved into the actual wall surface of the building, it has been executed in a large scale so that the children might readily view it. Subjects like a stork (Lancashire School) or dancing girl (Essex School) have become a constant delight to the children. In both cases, the work was carved on the site in special bricks of greater strength and thickness. Carving in wood or stone has a great attraction for children and can provide an excellent stimulus for the development of a real understanding of beauty in form and material.

It might be of value at this point to briefly discuss some of the schools in the various localities visited.

COVENTRY

The problems confronting Mr D. E. E. Gibson, County Architect and his staff at Coventry were totally different from those of the other groups. Due to the extensive war damage (Coventry suffered tremendously during the war) there arose a great demand for new schools. The situation required the immediate design of a structural system that could be erected quickly by relatively inexperienced labour. The final solution, a light steel frame prefabricated in type, was the first used in the Henry Parkes Primary School at Canley (planned in 1947 and completed only in 1950). This frame was the result of a close co-operation with the Brockhouse Engineering Company of Southport, England. It was designed to reduce the total steel tonnage of the building to a minimum (a 40 per cent saving was anticipated). Therefore, light steel strip mostly 10 gauge was selected. This allowed all of the structural units to be built up of foldings, formed where necessary into box sections of minimum overall dimensions. All sections are

factory-produced, and it is possible to erect complete classroom wings with available site labour, without the use of a lifting tackle.

Exterior walls (non structural) are usually brick with cavity construction or hollow clay block (again of cavity construction) cemented externally and plastered internally. All interior partitions are of hollow block plastered. Roof sections are either of corrugated reinforced asbestos sheeting with an underlayer of insulation board or of steel decking with insulation board on both sides, bituminous felt being the exterior finish.

HERTFORDSHIRE

In the immediate post-war period, Hertfordshire, (under the able direction of Mr S. H. Aslin, County Architect) like the other English counties, was faced with the acute shortage of schools. Beside the effects of bombing, lack of repairs and general rise in birth rate, the development of war industries and the policy of creating new towns in counties around London, made the problems more acute here than in most regions.

A "Meccano" type of construction based on an 8 foot 3 inch module has been adopted in all schools. This module, employed by most authorities has been determined largely as a result of the recommendations of the Wood Report 1944 and the fact that steelwork manufacturing plants were already jigged for this size. The framing members consist in the main of stanchions (assembled from 2 inch x 2 inch angles held together by angle welded to outside angles at regular intervals) beams, cross bracing and ties cantilever eave outriggers (T sections) and horizontal cladding bars (to which exterior materials are bolted). Of particular interest are the beams of channel section for the top flange and flat plate for the bottom flange; the flanges separated by welded diagonal lacing. The open webs do not obstruct the view, and are left exposed to allow free passage for mechanical pipes.

Wall slabs of precast concrete slabs are finished externally with either, Derbyshire spar, rough tyrolean finish or coloured cement. They are set either vertically or horizontally and are joined in a tongue and groove fashion, the whole portion being bolted to the cladding bars. A "wet" construction has been completely avoided, and interior wall linings are of fibrous plaster three-quarter inch thick back with aluminium foil. All interior partitions, are of a 2 inch thick fibrous plaster with a wood wool core finished with oil paint. Stanchion casings are three-quarter inch fibrous plaster. A wide range of flooring materials have been used, including hardwood, accotile (type of mastic tile) quarry tile and grey marble.

ESSEX

The programme of the Essex County Council (Harold Conolly, County Architect) is certainly the most extensive of all authorities visited. Beside the regular demands the group must also furnish schools for five new housing estates, of approximately 6000 houses each being built by the London County Council, and two new towns, Harlow and Basildon, being planned as satellites in conjunction with the London Master Plan.

Thus, with such a gigantic undertaking, it was obvious

that a new technique in the design and construction of the schools would be required. The ideal of individually designed jobs was, for the moment, but a luxury, and some degree of standardization would have to be introduced. Nevertheless, it has not employed to the extent of the Coventry or Hertfordshire groups. "There is no 'standard' Essex plan, nor is there any system of complete prefabrication of schools in the work of the department. It is held that each school, whether for primary or secondary education should possess its own individual features and architectural appearance if it is to build up a special tradition as successive generations come and go."^a



CLASSROOM INTERIOR


School at Hitchin, Hertfordshire
C. H. Aslin, County Architect

Ten various forms of construction have been used for primary and secondary schools, mostly variations of systems of precast concrete, insitu concrete and steel framing. The system of forward or bulk ordering, popular with the Hertfordshire group, has been practiced most extensively. This ordering not only improves deliveries but also helps by affording reduced prices.

A word might also be said for the part played by separate companies in the school programme. Mention has already been made of the Brockhouse Engineering (Southport) Limited who along with the County Architects of Coventry has devised a unique prefabricated structural system. The Bristol Aeroplane Company Limited has also devised a unit construction for schools. The aim of the Company has been to provide the educational authorities with a range of standard units which may be assembled in several ways to produce the various components of a modern school. Realizing the importance of flexibility, no attempt has been made to produce a standard classroom or school. In general, aluminium wall panels and roof trusses have been designed in a four foot module. Various spans of the trusses are readily available. The wall panels are, in reality, an insulated and sound-proof sandwich.

(continued on page 151)

^a Architectural Times, November, 1949.




PERSPECTIVE LOOKING S.W.

JOHN B. PARKIN ASSOCIATES
ARCHITECTS




OAA HEADQUARTERS

BUILDING



1st FLOOR



GROUND FLOOR

After sixty years of rented premises, the Ontario Association of Architects has decided to build. With that in mind, a site was purchased in a central location near to Bloor Street, Toronto, yet partly surrounded by park land. A ravine road skirting the park will take care of parking.


To arrive at a design, a competition was held with Messrs Marani (Chairman), Arthur and Brown as Assessors. The accommodation required consisted of offices for the OAA and (temporarily) for the RAIC, with a Board Room

COMPETITION


shared by the two organizations. Other accommodation consisted of Lounge, the Library, two bedrooms for out of town members like the PRAIC, the POAA or lesser fry, and houseman and wife. It was a condition of the competition that the library should be conveniently supervised from the OAA office. The drawings illustrated are those of the winner, J. B. Parkin Associates, and the three runners-up, Messrs Hassig, Page & Steele, and Worsley. Altogether thirty-seven persons or firms competed and the standard of design was very high.




PAGE & STEELE
ARCHITECTS



2nd FLOOR







CHARLES R. WORSLEY
ARCHITECT




GEORGE HASSIG
ARCHITECT




1st FLOOR




1st FLOOR





2nd FLOOR



2nd FLOOR



PLAN $\frac{1}{2}$ " 1'-0"




PANELLED WALL WHEN BAR IS CLOSED

WEST WALL ELEVATION
SCALE: $\frac{1}{2}$ " 1'-0"

COCKTAIL BAR

RESIDENCE FOR MR. & MRS. I. SUSSMAN TORONTO



'A - A'

SECTION AT 'B B'
SCALE $\frac{1}{2}$ " 1'-0"

PAGE & STEELE
ARCHITECTS TORONTO

NEWS FROM THE INSTITUTE

ALBERTA

The government of the province of Alberta, during its past session, undertook an examination of the Acts under which various professional associations operate, including the Architects' Act. The Alberta Association therefore conferred with the minister in charge of this work. Committees met, taking legal advice, and a number of changes were suggested both on the part of the government and on that of the association. These changes were apparently satisfactory to both these parties. But, at the close of the session, the bill had not been introduced in the house. The old act therefore remains unchanged. This is a disappointment for the Alberta Association of Architects for they hoped to have some very definitely beneficial changes made.

One of the proposed changes was to a clause requiring the employment of an architect for all buildings exceeding the cost of ten thousand dollars. This clause had become somewhat of a headache to building inspectors in issuing their permits to build. Besides the difficulty in determining costs they had to face a variety of ways in which applicants endeavoured, more or less successfully, to evade the requirement. It was therefore thought to be sounder policy to base the need for the employment of an architect on the character and extent of the work. Fire-resisting construction, extent of floor area and the length of clear spans involved were considered to be a better basis to go on. It may be within the competence of municipal bylaws to cover this requirement by their own regulations. But these can only apply locally and have no force over large areas of the province where there are no regulations, although they are more needed there than elsewhere.

Another proposed change in the Act was in the clause regulating the fees authorized for admission to practice and the annual fees. It was mutually agreed that these were inadequately low. They were set at a time when the Association was a very small body and when money went much further than it does today. The present much larger number of members increases the income of the Association but it also increases the work and the responsibilities of the Association.

Older members of the Association will recall that it struggled for quite a number of years with a substantial balance, in the red. On one occasion the Association had invited the RAIC to hold its annual meeting in Calgary. It is said, and can be believed, that the Calgary members, with the hospitality characteristic of that city, engaged the credit of the Association in a delightfully open-handed way. To this was attributed the blushing tint of the financial statements. By some strange magic the red at last turned to black, even on the meagre fees then, and still, in vogue and (touching wood) the black still leads.

It is to be hoped that the fact of the revision of the


Architects' Act not having been presented to the House does not mean that the idea of revision has been entirely dropped.

Cecil S. Burgess

INDUSTRIAL DESIGN: 1951 BC-AD 1951

It is just possible to describe this Exhibition in the space of a book review if one takes note of its two main aspects only.

Three-quarters of it traces the history of design from the most ancient period with its limited materials, tools and programme to that of the greater potential of the present day. All this is done on 35 demountable panels of bent perforated masonite, aluminum angles and African mahogany shelves. The active co-operation of the Royal Ontario Museum and the National Gallery of Canada gives this section an authority worthy of its function of



Bob Howard ref. No. 14

informing Canadians on this increasingly important subject. Along with its review of product design, the Exhibition shows the development of such contributing factors as sources of power, the history of machines and hand-craft, typography, packaging, and architecture. Elder architects may remember George Hansom, architect of the handsome Town Hall of Birmingham, who also designed the hansom cab. Younger ones will hail the contemporary architect Eames and his contribution to furniture design.

Throughout all, the four timeless aspects of Appearance, Performance, Production and Presentation are illustrated by a series of highly selective examples of fine design.

The second section tells of industrial design as an established profession, having the solid support of the highest forms of promotional and educational organization in Great Britain, the U.S.A., and Canada. In Canada, the

now permanent N.I.D.C. will occupy the ground floor of the Laurentian Building in Ottawa. Indeed, 1951 is a momentous year in the history of Canadian design development.

Architects in any town having space for the Exhibition should ask the National Gallery to send it for their fellow citizens to see. It has been admired and appreciated where it has been shown.

G. Englesmith

POST-WAR SCHOOL PROGRAMME IN ENGLAND

(continued from page 145)

They consist of an aluminium inner skin, thick layer of glass fibre, one layer of building board, and an outer skin of aluminium.

The system certainly is ingenious in concept and offers many opportunities, particularly the saving of time in erection (it takes one quarter the normal building period to erect). However, it would be most discouraging if this system, in its present mode was too readily utilized. It is quite true that variety is achieved by colour and part of the school being built of traditional type construction, but the overall effect is still obvious—one of complete standardization. Until the time when the structure becomes more versatile in concept, every school will essentially appear the same. The overall success of the initial scheme makes one confident that still more research will



CLASSROOM WING

Mixed Junior Infant & Nursery School
Canley, Coventry
D. E. E. Gilson, Architect

be employed until a unit has been perfected that carries more warmth and human spirit with less metallic glow and factory appearance.

In America, where conditions are totally different, prefabrication, in any large scale should be completely avoided in all school design. Environment is the all important part of education. It is up to the architect designed school to teach our children how to live.

In conclusion, the following remarks by Mr H. Conolly (Essex County Architect) admirably express the ideals of all English architects interested in school building.

"We have tested many forms of new building techniques to provide the number of schools needed in the time available, and to experiment as much as possible. We feel that

it is too soon to fix our building programme exclusively to one or two systems. And so we go on, always searching for better plans and better components, in the hope that some day we shall find the ideal in both. The ultimate test of our work is, do our buildings help John and Mary, our real clients, in the big job of growing up? And that is not for me to say."

ACKNOWLEDGEMENT

The Editorial Board wishes to thank Mr Harland Steele most heartily for his advice and assistance in the organization of the School issue.

CONTRIBUTORS TO THIS ISSUE

John H. Bonnick graduate of the School of Architecture, University of Toronto. First recipient of the Goulstone Fellowship, for the study of Architecture in England. Recently completed an extensive Architectural tour of England and Europe, specializing in schools. Has worked for Architects in Boston, U.S.A., and Toronto. At present in the office of Gordon Adamson, Toronto.

William W. Caudill received degrees from Oklahoma A&M College and MIT 1937, 1939 respectively. Member of AIA Committee on School Buildings, National Council on Schoolhouse Construction, and Texas School Plant Study Committee. Organized firm, Caudill and Rowlett in 1946.

William M. Pena attended A&M College of Texas and received B.S. in Architecture in 1942. Returned after service in the Army to receive B. of Architecture in 1948 and was awarded the school medal of the American Institute of Architects that year. Joined firm of Caudill, Rowlett and Scott in 1948.

A. Leslie Perry was born and educated in Montreal, and a graduate of Architecture, McGill 1923. He was attached to offices of Nobbs and Hyde Architects, Montreal and George B. Post and Alfred C. Bossom Architects, New York City. He has been in business since 1925 part of which time was in partnership with Messrs Luke & Little, Architects and for the last nine years has had his own office.


Francis G. Reed, born in Ohio of Canadian parents and educated in Saskatchewan. Graduated University Manitoba, 1931, B. Arch. Joined Lighting Service Dept. of The Hydro-Electric Power Commission of Ontario in 1938 as Lighting Designer, and is now Assistant Lighting Supervisor. After his discharge from the Army and still on leave of absence from the Ontario Hydro, he spent one year in the offices of W. L. Somerville and Craig & Madill.

Now in charge of the technical operation of the Commission's Lighting Service Department and principally occupied as a lighting consultant to the Ontario Department of Education and to architects and their consulting engineers.

Facts by Pilkington about Glass FOR ARCHITECTURAL STUDENTS

VOL. 2 — No. 1
THERMOPANE
GLAZING
DETAILS AND DATA

DETAILS FOR GLAZING EITHER STATIONARY OR MOVABLE WOOD SASH WITH THERMOPANE



The characteristics and uses of Thermopane window insulating units were dealt with on pages 22, 23, 24 and 25 of Volume 1 and examples of Installation were shown on pages 43 and 44 of the same. This page gives details of installation. Thermopane units should be set on soft surface setting blocks. These blocks should be the same thickness as called for by B in table below and of a width equal to the thickness of the Thermopane unit. They should be located in from each corner and centered a distance of one-quarter the horizontal edge of the unit. (Per illustration.) Soft rot-proofed wood, soft lead, or metal blocks with soft lead tops are used.


GLASS CLEARANCES

Since Thermopane is a factory fabricated unit, it is not subject to further processing and its dimensions cannot be changed at point of use. Therefore, proper glass clearances must be allowed on all edges.


RABBIT DEPTHS

So that the metal seal does not show, sufficient rabbit depth must be allowed. To achieve this, the metalized edge depth must be added to the glass clearance.

The following chart illustrates these points:



*Drawing is one-quarter
actual size*
**FIXED PICTURE WINDOWS
AND/OR WINDOW WALLS**



*Drawing is one-half
actual size*
**DOUBLE HUNG, CASEMENT
AND/OR SMALL FIXED
SASH**

Symbol and Explanation	Glass Thickness					
	24 O.Z. 1/8" Plate 1/8" Pat- terned	1/8" Sheet Glass		1/8" or 1/4" Plate 1/8" or 1/4" Patterned		
Glass Sizes	under 80 united inches†	under 80 united inches†	from 80-120 united inches†	under 80 united inches†	over 80 united inches†	over 120 united inches†
A—Glazing compound Bed	1/16"-1/8"	1/16"-1/8"	3/8"	3/8"	3/8"	3/8"
B—Glazing Clearance (all edges)	3/8"	3/8"	3/8"	3/8"	3/8"	1/4"
C—Metalized Edge— Depth	3/8"	3/8"	3/8"	3/8"	1/2"	1/2"
D—Total Rabbit Depth B+C	1/16"*	1/16"*	3/8"*	1/16"*	13/16"*	7/8"*

†Sum of length plus width. *Allowance made for dimensional tolerance.

AIR SPACE

1/4" or 1/2" air spaces can be furnished on small units, but for building exteriors sizes 48" wide and over will be furnished with 1/2" air space only.

Further details on the installation of Thermopane will be given in Vol. 2 No. 2



Pilkington Glass LIMITED

• HEAD OFFICE — 165 BLOOR ST. E. TORONTO, ONTARIO • BRANCHES: SAINT JOHN, N.B.
HALIFAX, MONTREAL, ROUYN, KINGSTON, TORONTO, HAMILTON, ST. CATHARINES, LONDON, FORT WILLIAM, WINNIPEG, REGINA, CALGARY, EDMONTON, VANCOUVER
• AGENTS: KITCHENER: TAIT GLASS CO. LTD. • VICTORIA: O'NEIL GLASS and PAINT, LIMITED • PETERS & SONS ST. JOHNS, AGENTS IN NEWFOUNDLAND SINCE 1890

Rosco WINDOW WELLS

the most Efficient and Economical Window well on the market today!

Nowadays, everyone concerned with building is more aware than ever of the rising material and labor costs. Realizing this, and because of the acute housing situation, the Roofers Supply Co. Limited have designed the Rosco Window Well.

When Rosco Window Wells are installed, dreary basement rooms come to life with proper illumination — without the extensive material, labor and maintenance costs required when thick masonry walls are built. And the bright, galvanized surface of Rosco Window Wells, reflect more light into the basement than any other well structure.

Rosco Window Wells are available in both the "round" type and the "straight" type. The "straight" type is more practical to use with wider windows where yard space is limited.

Write today for completely illustrated catalogue containing prices and installation instructions.



THE ROOFERS SUPPLY CO. LIMITED


TORONTO

MONTREAL


LONDON

OTTAWA




QUEBEC



ROSCO "ROUND" TYPE



ROSCO "STRAIGHT" TYPE





We doubt that you've worked on many birdhouses lately.

We haven't helped heat any, either.

But we can help heating engineers and contractors provide the proper thermal environment for any client—anywhere—in any kind of structure.

We have a lot of literature on the automatic control of all phases of heating, ventilating and air conditioning. Information you should have in your files.

And we have a lot of very well informed control engineers—in our Canadian offices—who have a lot *more* information right at their finger tips.

We sincerely believe we can help you on any project that poses problems of control of any kind—for *control* is Honeywell's business.


So, why not *talk to Honeywell*? Why not *write* to Honeywell for complete information on the equipment discussed in the column across the page? And why not do it *now*?

MINNEAPOLIS
Honeywell

First in Controls


BRANCHES IN HALIFAX • MONTREAL • OTTAWA • HAMILTON • LONDON • WINNIPEG • CALGARY • EDMONTON • VANCOUVER

We can't help you heat bird-houses, but we can help you plan better control for your heating systems. So fill out the coupon below and send it to us for



Facts you need—FREE!


Honeywell Electronic Moduflow can give your customers the finest automatic temperature control available. In this system, the smallest change in temperature indoors—or outside the house—activates sensing elements which signal the Electronic Relay Amplifier. The amplifier "interprets" the signals—and controls the heating plant with split-second precision. That's why Honeywell Electronic Moduflow provides the owner with uniform comfort—even in the most changeable weather.



A highly adaptable system, Electronic Moduflow is superior to all other home temperature control systems for these two reasons: 1. All sensing elements are electronic—which means they're up to 100 times more sensitive than mechanical controls. 2. Units of the systems compensate for all three important control factors—temperature changes outdoors, load shifts indoors and structural heat loss.

Honeywell Zone Control is an excellent way to achieve uniform comfort and economy in any type of structure. Tailor-made systems are available for homes—and for institutional, commercial and industrial buildings.

In the Honeywell Zone Control System, each zone is equipped with its own set of controls, including an individual thermostat. This means you can maintain the desired temperature in every part of the structure despite wide differences in exposure, use, occupancy and structural heat losses.



And Zone Control makes it possible to lower temperatures for economy's sake during the part of the day when certain sections of the building are not in use.

For additional, specific information on Honeywell Electronic Moduflow and Honeywell Zone Control, fill in and mail the accompanying coupon now. It will bring you material you'll want to read—and keep handy in your files.

MINNEAPOLIS-HONEYWELL REGULATOR CO. LTD.

Leaside, Toronto 17

Gentlemen: Please send me information on

☐

Electronic Moduflow

☐

Zone Control

Name _____

Firm Name _____

Address _____

City _____ Prov. _____

STERNSON FLEXCELL



Superior Non-Extruding Expansion Joint

FLEXCELL is specified by Architects and Engineers for expansion joint because

1. FLEXCELL will not extrude under compression.
2. FLEXCELL adheres to the concrete.
3. FLEXCELL re-expands repeatedly.
4. FLEXCELL is economical.
5. FLEXCELL stays in place.
6. FLEXCELL is easy to handle.
7. FLEXCELL presents no complications.

How to Insulate a Concrete Slab

FLEXCELL is water-proof and does not deteriorate in the presence of moisture. This makes it an ideal insulation for concrete slabs.



Radiant Heating in Concrete Floors

To prevent heat losses a minimum of two layers of 1-inch Flexcell board should be provided at the edge. Also, the use of Flexcell insulation under the entire heated floor area is recommended.

STERNSON STRUCTURAL SPECIALTIES LIMITED

Brantford, Ontario

Structural Sales Division
G. F. STERNE & SONS LIMITED
BRANTFORD, CANADA

MONTREAL
Tel.: Flitzroy 8581

MONCTON

TORONTO
Tel.: Kingsdale 4672

Associate Western Canada Manufacturers
CANADIAN CONSTRUCTION PRODUCTS LTD.
VANCOUVER, B.C.

MITCHELL-CLERK ALUMINUM WINDOWS



THE ROYALITE OIL CO., LIMITED BUILDING, CALGARY, ALBERTA

Stevenson and Dewar, Architects

Watson Construction Co., Engineers and General Contractors

THE ROBERT MITCHELL Co., LIMITED • MONTREAL

They Chose



BECAUSE . . . "Kalistron" solves all *three* major problems of wall and furniture coverings in hospitals and other public buildings.

1. **Maintenance** . . . Heavy traffic areas are kept in spotless condition with minimum effort.
2. **No Traffic Interruptions** . . . Traffic areas are not immobilized by recurrent repairs as required by ordinary wall treatments.
3. **Decoration** . . . Unlimited colour range. Colours are fused to *underside* of hard-wearing Vinylite assuring maximum protection against surface wear and abrasion.

In the Sick Children's Hospital, Toronto, Kalistron was chosen for wall and furniture covering . . . in dining rooms, outdoor patients department, elevator lobbies and many other wall areas . . . and for all upholstered and office furniture throughout hospital.

PAUL COLLET & CO. LTD.
LAURENTIEN HOTEL, MONTREAL




Sick Children's Hospital, Toronto, Ont.
Govan, Ferguson, Lindsay, Kaminker, Maw, Langley, Keenleyside—Architects.
Hugh P. Rickard, Decorating Advisor.

Paul Collet & Co. Ltd., Dept. K4,
Laurentien Hotel, Montreal, P.Q.

Please send me FREE Nail-File Test (swatch of Kalistron plus actual nail-file).

NAME.....

ADDRESS.....



EATON'S

"Staput" Movable

SCHOOL DESKS

Designed by "Bargen"



COMFORT AND EFFICIENCY

The pupil is aided in correct posture by means of special designing that encourages body alignment. Top and seat may be raised or lowered to suit the individual student.



READILY MOVABLE

As one compact unit, the desk can be lifted and moved quite readily . . . so that schoolrooms can be used for more than one specific activity.



NATURAL SPACE ECONOMY

Takes up less space . . . yet provides lots of leg room, extra comfort and efficiency . . . and allows extra floor space for other essential equipment.



BEAUTIFULLY BALANCED

Scientifically designed to assure functional balance. This important factor eliminates noise . . . makes a pleasingly designed desk of unusual stability.

EATON'S CONTRACT SALES DEPARTMENT



Glidden

JAPALAC

Paints




• To all architects and particularly to students who may be embarking on their professional career, we offer the expert services of the Glidden Decorative Studio Service.

• If you have a decorating problem — a special color treatment for a single room or a whole building — here is a competent authority that will make recommendations with actual color schemes in miniature and complete details for their use. This service is yours for the asking at all times.

When you specify Glidden paints you can always depend on uniform, unvarying quality.

The Glidden Company Limited



Front door set "69" is one of several clean-cut Peterboro designs especially suited to commercial buildings. It is a masterly piece of workmanship in cast bronze, supplied in all standard finishes. Matching knockers, letter box plates and inside door sets are also available.



For 66 years Peterboro Lock has combined unique artistry with enduring quality to create Canada's most distinctive and popular builders' hardware

Manufacturers of
Builders' Hardware • Cabinet Hardware • Padlocks

12-49

THE PETERBORO LOCK
MANUFACTURING CO. LIMITED
PETERBORO - CANADA

Put your light sources in the ceiling!

GOOD QUALITY ILLUMINATION

MODERN SPACIOUS APPEARANCE



Install

GENERAL ELECTRIC


TROFFERS

Wherever modern, efficient lighting is required, G-E Troffers in the ceiling will provide easy, comfortable seeing at reasonable cost.


When you are planning a new building or renovating an old one, install modern low-cost General Electric Troffers. You get good quality illumination *plus* an airy, spacious appearance. In stores, showrooms, offices or schools, Troffers flush-mounted in the ceiling will contribute to a roomier, more attractive interior because ceilings are left free of hanging fixtures.

You can have Troffers installed as single units in small rooms or in unbroken lines where continuous rows of light are needed. Each unit is provided with hinged louvers or glass panel assemblies which can be readily opened for easy cleaning and maintenance.


Write or phone your nearest C-G-E Office for additional information.



Each Troffer comes with easily detached baked white enamel reflector.



Hinged louver assembly provides excellent shielding of lamps, with low brightness contrasts between ceiling and troffer.



Hinged glass panel assembly gives a pleasing ceiling appearance, with full shielding of the lamps.

49-FJ-2

CANADIAN GENERAL ELECTRIC CO LTD

Head Office: Toronto — Sales Offices Coast to Coast



CENCO-SLATE

CANADIAN
MANUFACTURED

CHALKBOARD

"Cenco-slate" assures long and satisfactory service. Its manufacture combines the fire-safe, permanent and economical qualities of asbestos fibre, cement and other indestructible minerals.

"Cenco-slate," made in the form of solid sheets, is rock hard and just as enduring. Its superb writing surface is finished in a permanent black or green that distinctly shows the writing from any angle without glare or reflection. It retains its color despite constant usage, and chalk marks are easily erased.

"Cenco-slate" comes in three and one-half and four feet widths (heights) and in lengths of four, six and eight feet.

"Cenco-slate" is easily installed on brick walls, studding, sheathing, or practically any kind of construction.

"Cenco-slate" being a Canadian product costs less than similar imported materials.

• • • • •

If you are interested in school construction, specify "Cenco-slate" to assure chalkboard satisfaction. Samples and further particulars will be provided upon request.



Hendry Division




CENTRAL SCIENTIFIC COMPANY
OF CANADA LIMITED

Successor to The Geo. M. Hendry Co. Limited

146 KENDAL AVENUE, TORONTO 4

7275 ST. URBAIN STREET, MONTREAL 14

1076 GRANVILLE STREET, VANCOUVER



What is the hidden Eldorado quality?

You cannot see it, but you can feel it in the way Eldorado works for you—easily, almost effortlessly.

And you can see its results in your drawings and blue prints.

It means crisp, sharp, even lines every time, all the time.

It means non-feathering, non-crumbling leads, standing up under pressure.

The hidden quality is TYPHONITE! Drawings made with *Typhonite* Eldorado leads insure clean, easy-to-read blueprints. Made in 17 degrees 6B to 9H. Order Dixon's *Typhonite* Eldorado pencils from your regular source of supply.

DIXON'S TYPHONITE ELDORADO

Eldorado Pencils are favourites with engineers and draftsmen everywhere. If you would like a sample, just send your name and address and the degree of Dixon Typhonite Eldorado Pencil you would like to try.

Made in Canada by

DIXON PENCIL COMPANY LIMITED
MONTREAL - NEWMARKET - TORONTO - VANCOUVER

BAR AKWA

New Product Stops CAPILLARY ACTION

IN mortar, masonry, concrete, brick, wood — in any porous building material.

Bar/akwa is a clear, colourless liquid which, when applied to porous materials, penetrates deeply and stops capillary action. Thus, moisture is completely stopped from entering the material. Because Bar/akwa is clear, colourless and because it penetrates, it does not change the appearance of the material to which it is applied in any way. It is not a film or a surface and therefore lasts the lifetime of the material to which it is applied.

Now, it is possible to retain the appearance of new buildings by this simple, effective means of eliminating the damaging effect of moisture including efflorescence. Mortar and brick are waterproofed and so strengthened.

Bar/akwa is not an integral waterproofing. It is applied by brush, spray or dipping and is absolutely non-toxic to skin or membrane.

Bar/akwa is developed and produced by



LIMITED

PAINTS • VARNISHES • ENAMELS

330 Carlaw Avenue
TORONTO • ONTARIO



North York, Toronto: Formica* desk tops are a feature of the Glen Park School. Their unusually-smooth, long-wearing surfaces are easy to clean and are unharmed by ink. *Trade Mark.

Eaton's of Canada, Supplier



Distributed in Canada by
and company limited
TORONTO • OAKVILLE • MONTREAL

Check with LADORE for SPECIALIZED BUILDING PRODUCTS

Ornamental Iron Railings

Hawkins Adjustable Railings fit almost any size and slope of steps. They bring new beauty and strong protection to indoor stairways, outdoor porches and porch steps.



Modern Steel Bathroom Cabinets

Sparkling plate mirrors, newest smart designs, indirect lighting, best quality chrome.

"Over-the-Top" Garage Door Hardware

Ladore-equipped garage doors open at a touch — in 3 seconds and in any weather. "Over-the-Top" installations automatically lock both jambs and balance the door in any desired position.



Write for illustrated folders on these and on plate glass mirrors, sliding door hardware and bathroom accessories.

503

LADORE & COMPANY LIMITED
354 CHILVER ROAD
WALKERVILLE ONTARIO



Give every student the advantage of scientifically designed classroom furniture. Stan-Steel School Desks are built in five sizes to accommodate students from first grade to university, the design meeting professional approval.

★ Paul-Emile Laflamme, M.D., C.M.C., C.M.R., graduate of the hospital of Vienna, writes: "I have found this desk to contain a posture seat curved to fit the spinal curvature of young students whose immature backs need firm support."

★ J. O. McDonald, M.D., C.M., says: "The convexity of the back of the chair should make the pupil take an upright position and so will do away with the various acquired Scoliosis which were so prevalent in children using the straight backed chairs."

In addition, the new Stan-Steel desk has a rigid tubular steel frame with clean-cut design which facilitates janitor operations. For further information, write now to . . .

★ Complete statements may be examined at any time.



STANDARD TUBE AND LIMITED
 HEAD OFFICE AND PLANTS AT...
 WOODSTOCK ONT. PHONE 1975

BRANCHES-

TORONTO - 1663 DUFFERIN ST. PHONE KE. 3549
 MONTREAL - 754 WELLINGTON ST. PHONE UN. 6-5721
 OTTAWA - 121 SLATER ST. PHONE 4-2220




for customers who want the
added convenience of a powder room
or extra bathroom...

CRANE - the Preferred Plumbing

offers a complete range of smartly-styled and dependable fixtures and fittings to meet varying requirements—together with all the necessary valves and piping that go with them.

EASY TO INSTALL and to maintain, modern Crane toilets and lavatories, supplied with choice of trim, are sure to win lasting customer approval and appreciation, for their beauty and utility endure.

For complete information on the variety of styles and sizes available, ask your Crane Branch.



CRANE LIMITED • GENERAL OFFICE: 1170 BEAVER HALL SQUARE, MONTREAL
18 BRANCHES IN 10 CANADIAN PROVINCES

1-5008

CRANE

VALVES • FITTINGS • PIPING
PLUMBING • HEATING

NATION-WIDE SERVICE THROUGH BRANCHES, WHOLESALERS and PLUMBING AND HEATING CONTRACTORS


C-I-L COLOUR CONDITIONING in Ingersoll's Alexandra Hospital



Nurses' station, corridor and elevator area. Walls finished in C-I-L SEMI-GLOSS Cool Green; dado in Cement Enamel Green. Architect: L. G. Bridgman. General Contractor: Schwenger Contracting. Painting Contractor: Clarke Bros. Furniture, furnishings, etc. Robt. Simpson Company Limited.



Nursery walls are finished in C-I-L SEMI-GLOSS White; cubicles in Dainty Baby Blue Enamel.



Solarium. Walls and ceiling finished in C-I-L SEMI-GLOSS Cool Green, a special C-I-L Hospital Colour.



C-I-L Hospital Colours selected for the new Alexandra Hospital, Ingersoll, Ont., have won most favourable comments from hospital officials, as well as patients and visitors.

Says Mrs. R. L. Smith, hospital superintendent: "We used C-I-L Hospital Colours throughout (with some minor alterations through the addition of white). Visitors comment that the colours give the hospital character and a pleasant atmosphere, and patients say their rooms are lovely. This is very important as people who are ill are frequently out of mental balance. Colour brightens their mental outlook and cheers them up."

Comments from Mrs. P. M. Dewan, chairman of the hospital committee, and Dr. H. C. Furlong, chief of staff, are equally gratifying. "We are so pleased with the colours," says Mrs. Dewan, "and what they have done for our hospital. All concerned have spoken highly of the way it is furnished and particularly of the colours."

C-I-L ADVISORY SERVICE

The Paint and Varnish Division of CANADIAN INDUSTRIES LIMITED welcomes the opportunity to assist in developing colour treatments and suggesting suitable finishes. Write or phone your nearest District Office. *Halifax, Montreal, Toronto, Winnipeg, Regina, Calgary, Edmonton, Vancouver.*



51-PVR-2

CANADIAN INDUSTRIES LIMITED • MONTREAL
"Serving Canadians through Chemistry"

There's Always SOMETHING MORE in a *Josam* Product

Josam Products are the leaders in the field because they give you more than you would expect. They are more thoroughly engineered, better constructed, and easier to install. Here's a typical example of one out of many hundreds of Josam Products made to meet every drainage requirement!



JOSAM BACKWATER VALVE

The Josam Backwater Valve is the one valve you can install with complete assurance of reliability because of its superior design. Highly sensitive, self-cleaning, stainless steel bearings will not corrode or stick — allow valve flap to close with slightest backflow, preventing entry of backwater into drain lines or basement. Flap revolves, cleaning itself with each discharge of water, assuring positive closing. Leveling pads and trough permit easy and accurate leveling in installation. Use Josam Backwater Valves on your next job — you'll save time and make more money! Send for literature today.



Series 1180-T

OVER 2000 DIFFERENT TYPES OF *Drainage Products* TO MEET EVERY DRAINAGE CONDITION




ROOF DRAINS
Top provides continuous drainage in spite of accumulated debris.



SHOCK ABSORBERS
To eliminate water hammer in pipe lines.



SWIMMING POOL FITTINGS
Inlets, outlets, gutters, overflows.



INTERCEPTORS
For grease, oil, hair, plaster and sediment.



BACKWATER SEWER VALVES
To prevent sewer contents from backing up into basement floors.



NON-CLOG FLOOR DRAINS
Assure positive drainage and warn of stoppage in advance.


For literature on any of the above, write Dept A
JOSAM CANADA LIMITED

Head Office: 267 Davenport Road,
TORONTO, ONTARIO, CANADA

Representatives Throughout the Dominion

SPECIFY MURPHY COLOR DYNAMICS

For your next
construction project



Years of research in the scientific application of color have promoted plant efficiency in industry and restful beauty in the home.

The Murphy Research Laboratories are available for your specific paint problems and the experience of Murphy technicians is at your service to find the right answer.

We invite you to take advantage of these services in applying color scientifically. Write to-day for your *FREE* copies of our interesting booklet on *Murphy Color Dynamics in Industry and Murphy Color Dynamics for the home* — just off the press.

The Murphy Paint Company Limited

Factories: Montreal • Toronto • Windsor • Vancouver

Branches from coast to coast

The addition of many items from the Bryant line of wiring devices to the familiar range of Smith & Stone products represents an extension of Double Diamond service to customers. Bryant devices are backed by the great reputation they have built through many years. Their manufacture and sale in Canada by Smith & Stone links two famous names in a complete service.

Order from your wholesaler

SMITH & STONE



LIMITED

FACTORY AND HEAD OFFICE: GEORGETOWN, ONTARIO
Sales Offices: Montreal, Toronto, Winnipeg, Calgary, Vancouver



ST. JOSEPH'S HIGH SCHOOL, TORONTO, ONTARIO
Architects: Page and Steele

LIST OF RECENT CONTRACTS:

HIGH SCHOOLS

Glencoe High School
Glencoe, Ontario
Architect: C. H. Gillin

Arva High School
Arva, Ontario
Architects: S. B. Coon & Son

Kenora-Keewatin District High School
Kenora, Ontario
Architects: Shore & Moffat

INDUSTRIAL

Canadian SKF Company Limited
Toronto, Ontario
Architects: E. C. Miller of T. Pringle & Son, Ltd.

Pilkington Glass Mfg. Co. Ltd.
Toronto, Ontario
Architects: Allward & Gouinlock

Canadian Admiral Corporation
Port Credit, Ontario
Architects: N. A. Armstrong & Sons

HOSPITALS

St. John's Convalescent Hospital
Newtonbrook, Ontario
Architects: Mathers & Haldenby

Alexandra Hospital
Ingersoll, Ontario
Architect: L. G. Bridgman

Peel Memorial Hospital
Brampton, Ontario
Architect: Chester C. Woods

Estimates gladly supplied with designs for all kitchen equipment, for hotels, hospitals, institutions and industrial plants.

HOSPITAL & KITCHEN EQUIPMENT COMPANY, LIMITED - 67 PORTLAND ST., TORONTO, ONT.

THE PAINTER'S BEST FRIENDS ARE THE...



At last! Oil paint performance with waterpaint ease! Easy flow . . . no painty odour . . . deep colours as well as pastel . . . a semi-gloss finish you can really scrub! Tested and praised by painters everywhere — the finest synthetic rubber finish on the market.

See your Wesco dealer for colour folder, or write us.

THE EASY WAY TO PAINT IS THE  WAY!



FAST DRYING

EASY TO APPLY

ECONOMICAL

WESCO WATERPAINTS (CANADA) LIMITED
2100 ST. PATRICK STREET, MONTREAL

HALF A CENTURY . . .

Fifty Years is a long time in the useful life of any flooring but there are thousands of TERRAZZO floors in use to-day which were installed over fifty years ago. They are giving the same service year after year. Carrying heavy traffic, wet or dry, inside or outside, requiring no expensive maintenance or special care.

Terrazzo is Not Expensive

Keen competition which has produced increased efficiency in the use of improved machinery and installation technique has kept costs down. First Class TERRAZZO Floors can still be installed as low as sixty cents per superficial foot in most sections of Canada.

The cost of any type of flooring plus the cost of a finished cement under floor in most cases equals this cost and when other factors are considered TERRAZZO becomes a must.

GOOD TERRAZZO REQUIRES SKILL

The following firms are equipped to handle any job large or small and their many years of experience and integrity assure your client of first class materials and skilled workmanship.

Quebec Marble & Tile Co. Ltd., Quebec, Que.
Art Tile & Ceramique Co. Ltd., Montreal, Que.
The Canadian Flooring Tile Co. Ltd., Montreal, Que.
De Spirt Terrazzo & Tile Co. Ltd., Montreal, Que.
North End Tile Co. Ltd., Montreal, Que.
The Pizzagalli Terrazzo Mfg. Co., Montreal, Que.
Smith Marble & Const. Co. Ltd., Montreal, Que.
Durie Mosaic & Marble Co. Ltd., Ottawa, Ont.
Ottawa Tile & Marble Co., Ottawa, Ont.
Brooks Marble & Tile Co. Ltd., Toronto, Ont.
Connolly Marble Mosaic & Tile Co. Ltd., Toronto, Ont.

De Spirt Mosaic & Marble Co. Ltd., Toronto, Ont.
Kent Tile & Marble Co. Ltd., Hamilton, Ont.
Bernard-Hill Tile Co. Ltd., Kitchener, Ont.
Bernardo Marble Mosaic & Tile Co. Ltd., London, Ont.
Colautt Bros. Ltd., Windsor, Ont.
Fabris & Marinelli Ltd., Winnipeg, Man.
P. A. Molaro, Winnipeg, Man.
Alberta Marble & Tile Co. Ltd., Calgary, Alta.
Columbia Tile & Terrazzo Ltd., Edmonton, Alta.
Empire Marble & Tile Co. Ltd., Edmonton, Alta.
The O'Neil Co. Ltd., Vancouver, B.C.

Send for 16-page Catalogue

THE CANADIAN TERRAZZO & MOSAIC CONTRACTORS' ASSOCIATION

TORONTO ONT., P.O. BOX 4, STATION K.

MONTREAL, QUE., P.O. BOX 123, OUTREMONT




**The Walls in this Lobby
are Beautiful, Permanent
and easy to clean**



**The Sensational Plastic Laminate With
The Canada-Wide Acceptance**

Ask anyone who has had experience with this lasting, dense, hard-surfaced Decorative Wall-board. Even the most particular architects, engineers and contractors will tell you how readily it can be installed on the job — on new or old construction. They'll tell you how easily it can be cleaned with a damp cloth.

But there's more to Arborite than this. It won't chip or crack . . . never needs painting or patching . . . and it's practically everlasting. For any surface where you want rugged beauty and no maintenance worries — *Insist on Genuine Arborite.* It's available in panels 4' x 8' and 2'6" x 8' in more than 30 different colours and surface designs.



ARBORITE Table Top Grade

... also a winner! Won't stain, discolour or be affected by grease, oil, alcohol, mild acids, alkalies. And it's cigarette-proof, too!

See your local lumber or building supply dealer, or write:

THE ARBORITE COMPANY LIMITED

385 Lafleur Ave., Ville LaSalle, Montreal 32, Que.

Ontario Sales Office: 159 Bay Street, Toronto

AC-41T

DEXTER RESIDENCE HARDWARE


for —

- *Dignity!*
- *Distinction!*
- and
- *A Lifetime of Service!*

When your buildings demand tastefully designed top-quality hardware to give them the perfect finishing touch, make your selection from the DEXTER TUBULAR range of modern, sturdy locks and latches.

Only DEXTER TUBULARS offer you ALL these 9 features —

1. Solid Brass Trim.
2. Zinc plated steel internal parts.
3. Two Big Coil Springs, for ease of operation and long life.
4. Uniform boring for both locks and latches.
5. Self-adjusting alignment, for ease of installation.
6. Unique self-locking set screws for knobs.
7. Shallow face-plate mortise.
8. Made in Canada.
9. Lifetime Warranty.



FOR FULL
INFORMATION
WRITE TO:—

**DEXTER
LOCK
CANADA
LIMITED**
•
GUELPH
•





Accuracy

LINKED closely to the precision jobs coming off the boards are the tools that assure accuracy of detail. One of these is the seemingly small pencil which looms large in the mind of a craftsman, as an important instrument of accuracy.


VENUS Drawing Pencils are engineered to give you drafting perfection without failure: accurately graded to assure uniformity in all 17 degrees... strong in performance... smooth and clean in action.



Put VENUS to the test on your drawing board. Send us a postcard or a note for two free samples. Specify degrees wanted.

VENUS DRAWING PENCILS

this practical
wood protection
reduces replacement
and repair ...




...by as much as 50%!

Double the effective life of lumber used in subfloors and other out-of-sight places in the average home — for less than \$150 — recommend and specify lumber treated with preservatives made from NUODEX Copper Naphthenate! These advantages assure maximum protection against wood rot, insure against expensive replacement and repair!

- *Safe to handle* — won't burn or irritate the skin.
- *Apply like paint* — by brush, spray or dip.
- *Longer lasting* — won't evaporate or wash out.
- *Paintable* — distinctive light green colour can be painted over.
- *No fire hazard* — will not increase inflammability of treated wood.

LOOK FOR THIS SEAL!

Preservatives made from NUODEX Copper and Zinc Naphthenates are marketed by many paint and chemical manufacturers in a variety of packages under many different labels. They can be readily identified by this silver seal which manufacturers attach to their packages to *certify* genuine NUODEX Naphthenate content.



SPECIFY WOOD PRESERVATIVES MADE FROM

NUODEX } COPPER AND ZINC
NAPHTHENATES

NUODEX PRODUCTS OF CANADA LIMITED, LEASIDE, ONT.

FOR DRIER, CLEANER MASONRY

Medusa Portland Cement Paint is made especially for basement walls, stucco and other masonry surfaces. With its Portland Cement Base, this water-resistant paint bonds itself perfectly to masonry surfaces —and will not flake or peel off.

Economical and easy to apply, it comes in black, white and six attractive colours.



MEDUSA

PORTLAND CEMENT PAINT

51-2

MEDUSA PRODUCTS COMPANY OF CANADA LIMITED
PARIS, ONTARIO

... FOR EVERY CONSTRUCTION PURPOSE

DESIGNERS
FABRICATORS
ERECTORS

SARNIA BRIDGE
OFFERS YOU A
SPECIALIZED
COURTEOUS
SERVICE

Prompt Quotations
Booklets on Request

STEEL

Sarnia Bridge Company provides a complete service for all standard steel requirements . . . riveted or welded steel for buildings, bridges, head frames, bins, hoppers, etc. that qualify for materials and construction in steel. Our engineering department will be pleased to help you with your problems.

SARNIA BRIDGE
CO., LIMITED
TORONTO SARNIA MONTREAL
CANADA



Suppliers of

SAFWAY SCAFFOLD
SAFWAY HOISTS
MASSILLON BAR JOISTS
STEEL — Designed, fabricated and erected





Architects: Marani & Paisley

**100% Frigidaire Refrigeration user
for more than 20 years...**

Ridley College chose Frigidaire for new Upper School kitchen

● Could there be stronger proof of the satisfaction Frigidaire refrigeration equipment gives? Yet Frigidaire records show many hundreds of cases such as that of Ridley College, where fifteen-year, twenty-year and twenty-five-year users have come back to Frigidaire for more equipment or replacement equipment.

Learn How a Free Analysis of Your Cooling Requirements May Mean Better Refrigeration At Less Cost


The type of refrigeration equipment used, and the kind of performance it gives, can make an important difference in the operation of any institution, business or industry. Frigidaire has developed a valuable service called the FRIGIDAIRE REFRIGERATION SECURITY

ANALYSIS which quickly and simply demonstrates the truth of this.

Consult your Frigidaire Commercial Refrigeration Dealer about it. He'll give you a clear-cut report based on a special analysis of your business or institution and Frigidaire's 30 years of experience with all kinds of refrigeration equipment.

From this analysis, you'll learn what type of equipment would be best — what replacements or additions, if any, are needed — how long it will take new Frigidaire equipment to pay for itself.

This valuable service is free. Call in your local Frigidaire Commercial Refrigeration Dealer today. Or mail the coupon.



A. A. Widdicombe & Son, St. Catharines, Ontario, who sold the original Frigidaire equipment to Ridley College 20 years ago, also made this latest installation.

Frigidaire Products of Canada, Limited
Dept. A,
Leaside, Ontario

I would like to take advantage of your
free Frigidaire Refrigeration Security
Analysis:

Name

Address C-540

City.....Prov.....



FRIGIDAIRE

Products of Canada, Limited, Leaside, Ontario
FRIGIDAIRE IS MADE ONLY BY GENERAL MOTORS



**FURNISHINGS
and
EQUIPMENT**

for all kinds of
public buildings.

Simpson's

SPECIAL CONTRACT DIVISION
TORONTO (Head Office)
HALIFAX, MONTREAL, LONDON, WINNIPEG,
REGINA, EDMONTON, CALGARY, VANCOUVER

Please direct all communications specifically to the
Special Contract Division



Woodman...spare that tree!

Today, home owners can enjoy the natural beauty of tree-shaded lawns and gardens without risking sewer blockage by tree roots. At no extra cost, No-Co-Rode Rootproof Pipe ensures permanently root-free sewers.

For septic tank systems, use No-Co-Rode Perforated Pipe—it is recommended by Health Departments, is permanent and easy to install and, as a foundation footing drain, will keep basements perfectly dry.

Stocked by leading plumbing and building supply houses
Distributed by

Alexander **MURRAY** & Company LIMITED

CRANE
LIMITED

NO-CO-RODE

ROOT-PROOF PIPE

UA9-51


Manufactured by DOMINION TAR & CHEMICAL COMPANY LIMITED Sun Life Building, Montreal

**PUBLIC BUILDINGS
AUDITORIUMS
SCHOOLS**

**INDUSTRIAL BUILDINGS
LABORATORIES
HOSPITALS**



DALEWOOD SCHOOL, HAMILTON



VICTORIA HOSPITAL, LONDON

FROM COAST TO COAST

THE "ORIGINAL" CEMENT ENAMEL

BY

CEMENT ENAMEL (CANADA) LTD.

142 ST. PATRICK ST., TORONTO

&

CEMENT ENAMEL (QUEBEC) LTD.

1452 DRUMMOND ST., MONTREAL




TRUSCON "Clerespan" Joists

Long on length...



Truscon "Ferrobord" Steeldeck being used with "Clerespan" Joists for ideal fire-resistant roof construction.



short on costs

Impart a sweeping new airiness to your structures . . . endow them with spacious floor areas unobstructed by intermediate supporting columns or pillars. Plan with Truscon "Clerespan" Joists, and get up to 64-foot clear reaches with adequate safety. Long spans such as these permit more efficient arrangement of partitions, display counters, stocks, machinery, etc., and make possible

the development of large, free, floor expanses for garages, bowling alleys and similar requirements. The number of structural elements required is substantially reduced. The shallow depth of "Clerespan" Joists also permits a saving in masonry work by reducing the required height of building walls. Free illustrated literature on Truscon "Clerespan" Steel Joists on request.

DOUBLE HUNG STEEL WINDOWS	TRUSCON	FACTORY SASH OF ALL KINDS
STEEL BASEMENT WINDOWS	STEEL	STEEL SASH OPERATORS
	COMPANY OF CANADA LIMITED	
WALKERVILLE • TORONTO • MONTREAL • HALIFAX • WINNIPEG • REGINA • CALGARY		

*For Aluminum,
Steel or Wood Windows*

SPECIFY
TREMGLAZE
MASTIC GLAZING COMPOUND
IN COLORS

NEEDS NO PAINTING


**DEPENDABILITY
PROVEN ON
ACTUAL JOBS
FOR OVER
10 YEARS**

On aluminum windows, Tremglaze meets Aluminum Window Manufacturers Assn. standards. Completed steel window installations cost no more with Tremglaze than with putty. Save on the paint contract—specify "Paint first—then Tremglaze". Put paint on the window where it belongs. CALL LOCAL TREMCO MAN—OR WRITE

NC 102a

THE TREMCO MANUFACTURING CO.
(Canada) LTD., TORONTO

Products and Methods for Building Construction and Maintenance



Bronze Fixture in Rotunda
of Thames Hall, London

Designed and Manufactured by

METAL INDUSTRIES LIMITED

24 Dunbar Avenue, Hamilton, Ont.

MUNDET

*When you think of
Insulation think
of MUNDET*

CORK & INSULATION LIMITED

Manufacturers & Contractors

**MUNDET
CORKBOARD**

**JOINTITE
PIPE COVERING**

C-4

TORONTO
35 Booth Avenue

MONTREAL
795 Versailles St.

Ernest Eagle *chases* GHOSTS!



DEMONS of the drawing board, these two little wraiths
haunted draftsmen's dreams . . . 'til TURQUOISE took over.

THE LITTLE LINE THAT *isn't* THERE

Somebody drew him, but he died. Burnt out in the intense glare
of the printing machine, he became a pale shade of his former self . . .
a here-again gone-again phantom that flits erratically across the prints.

But TURQUOISE lines stay put. Electronic graphite, super-refined in
Eagle's patented Attrition Mill makes even the thinnest line so opaque
and *solid* that it shows up . . . alive and hearty . . . on every print.

THE LITTLE LINE THAT *shouldn't* BE THERE

This is a stubborn little spirit. Drawn by mistake and erased,
he hides in the pores of the paper and pops out to pester you in the prints.
But unwanted TURQUOISE lines can be "killed" for keeps,
because there is no penetrating chemical
in TURQUOISE leads. All of the mark
is on the surface of the sheet—
a few strokes of an eraser remove it forever.

Write for a free TURQUOISE pencil or lead,
naming this magazine, your dealer,
and the grade you want.

EAGLE "CHEMI-SEALED"
(SUPER BONDED)
TURQUOISE

DRAWING PENCILS AND LEADS
EAGLE PENCIL COMPANY OF CANADA LIMITED

217 BAY STREET

TORONTO 1

CONCRETE WATERPROOFING BUILT-IN!

*All Concrete Below Ground Level
Should Be Waterproofed*

Medusa Waterproofing Paste or Powder, mixed with cement before pouring, forms a water-repellant film which lines the pores of the masonry and makes the whole mass completely waterproof. It costs only a few cents per bag of cement—cheap protection and satisfaction for builder and owner.



MEDUSA

WATERPROOFING PASTE & POWDER

51-3

MEDUSA PRODUCTS COMPANY OF CANADA LIMITED
PARIS, ONTARIO

This is for YOU!



All about
**PROPELLAIR
SKY
BLAST**

If you are in any way concerned with the removal of fumes, dust, heat or steam from industrial buildings you will find this R & M folder helpful and informative. It gives complete details on the ventilator with the new low silhouette. Let us help you to ventilate effectively, economically.

Send for your free copy of Bulletin No. 680/J15

THE ROBBINS & MYERS CO.
OF CANADA LIMITED
TORONTO BRANTFORD, CANADA MONTREAL
ELECTRIC MOTORS • PROPELLAIR INDUSTRIAL FANS • MOYNO PUMPS • DESK FANS • HOISTS AND CRANES

ARCHITECTS RECOMMEND FRANKI CAISSON PILES because "FRANKI PILES CARRY MORE TONS PER PILE"

Some of our recent Canadian Contracts:

Abitibi Power & Paper Co. extension, Sturgeon Falls, Ont.
C.N.R. Office Building, and Loading Platforms, Bonaventure Station, Montreal.
Arena, Montmagny, P.Q.
Post Office, St. Jerome, P.Q.
Monkland High School, Montreal.
Station, Farnham, P.Q., and Angus Shops extension, C.P.R.
St. Joseph Hospital extension, Sudbury, Ont.
Canadian International Paper Co., Hawkesbury, Ont.
Catholic Seminary, Amos, P.Q.

Biscuit Factory, David et Frere, Montreal.
Dominion Textiles — Burlington Mills, Sherbrooke, P.Q.
Steinberg Groceries, Cote des Neiges and Ontario Streets, Montreal, P.Q.
United Stores, Ontario and Bourbonnieres Streets, Montreal.
Hydro-Quebec Kanawaki Suspension Towers, Ville La Salle, P.Q.
Arena, Val D'Or, P.Q.
Hydro-Quebec, Service Centre, Jarry Street, Montreal.

Estimates Promptly Prepared

FRANKI COMPRESSED PILE COMPANY OF CANADA LIMITED

4911 Cote des Neiges Road
MONTREAL

168 Richmond Street West
TORONTO






Include

Safety in your building plans!


EXPANDED STEEL MESH

... the IDEAL PLASTERING BASE!

Millions of yards in use! Building owners across Canada praise the stability of PEDLAR'S Metal Lath and the enduring smoothness of plastered surfaces reinforced by this tough steel mesh.



Diamond
Mesh
Metal Lath



"PEDEX"
Corner Bead

Your building will be
more Valuable . . . more
Permanent with

PEDLAR'S

Fireproofing Materials

Value and economy in a multitude of uses

PEDLAR'S Plaster Saving Metal Lath has a small diamond-shaped mesh that forms a bond with the plaster with a minimum of plaster waste. It may be readily formed over curves and angles. Our "PEDEX" Corner Bead, the ideal bead to use with Metal Lath, is made with wide, expanded metal wings, permits keying of plaster right up to nose of bead.

Write for prices of these popular PEDLAR materials

THE PEDLAR PEOPLE LIMITED

557 SIMCOE ST. SOUTH, OSHAWA, ONTARIO

Montreal • Ottawa • Toronto • Winnipeg • Calgary • Vancouver



PROTECT THE OWNER,
Waterproof
The Foundations With

'PUDLO'
BRAND

**CEMENT
WATERPROOFING
POWDER**

FIRST COST ONLY EXPENSE

• • •

EASILY MIXED WITH CEMENT

• • •

NO ADDITIONAL LABOUR COSTS

• • •

ADAPTABLE TO ALL CEMENT WORK

• • •

LUBRICATES THE MIX

• • •

IMPROVES APPEARANCE

• • •

USED IN CANADA FOR OVER 35 YEARS

• • •

NEVER FAILED WHEN DIRECTIONS
FOLLOWED


For further information write

SPIELMAN AGENCIES, LTD.

420 LAGAUCHETIERE ST. WEST
MONTREAL 1

INDEX OF JOURNAL ADVERTISERS

	Page
American Tile & Rubber Co., Limited	37
Anaconda American Brass Limited	31
Arborite, The, Company Limited	58
Armstrong, S. A., Limited	11
Atlas Asbestos Company Limited	5 and 6
Banfield, Arnold and Company Limited	50
Bishop Asphalt Papers Limited	21
Brantford Roofing Company Limited	14
Brick & Tile Manufacturers' Association of Canada	25
Building Products Limited	34
Canada Cement Company Limited	29
Canadian General Electric Co., Limited	35 and 47
Canadian Industries Limited (Paint & Varnish Div.)	53
Canadian Johns-Manville Co., Limited	1
Canadian Metal Window & Steel Products Limited	10
Canadian Terrazzo & Mosaic Contractors' Association, The	57
Canadian Vickers Limited	22
Carrier Corporation Limited	16
Cement Enamel (Canada) Ltd.	62
Cement Enamel (Quebec) Ltd.	62
Central Scientific Company of Canada Limited	48
Collet, Paul, & Co. Ltd.	44
Cooksville Company Limited, The	8
Corbin Lock Company of Canada, Limited	15
Crane Limited	52
Cresswell Pomeroy Ltd.	17
Crowder, K. N., & Company Limited	2
Curtis Lighting of Canada Limited	28
Dexter Lock Canada Limited	58
Dixon Pencil Company Limited	49
Dominion Bridge Company Limited (M-M Div.)	Third Cover
Dominion Oilcloth & Linoleum Co. Limited	19
Dominion Tar & Chemical Company Limited	62
Dunham, C. A., Co., Ltd.	6
Eagle Pencil Company of Canada Limited	65
Eastern Steel Products Limited	38
Eaton, The T., Company Limited	45
Empire Brass Mfg. Co., Ltd.	9
Fiberglas Canada Limited	23
Franki Compressed Pile Company of Canada Limited	66
Frigidaire Products of Canada, Limited	61
General Steel Wares Limited	20
Glidden Company Limited	46
Gurney Dominion Furnaces Limited	18
Gypsum, Lime & Alabastine, Canada, Limited	32
Harbour Brick Company Limited	8
Hospital & Kitchen Equipment, Limited	56
Johnston, R. E., Co. Ltd.	3
Josam Canada Limited	54
Ladore & Company Limited	50
MacMillan, H. R., Sales Limited	30
Medusa Products Company of Canada Limited	60 and 66
Minneapolis-Honeywell Regulator Co. Limited	42 and 43
Mitchell, The Robert, Co. Limited	44
Modine Manufacturing Company	3
Mundet Cork & Insulation Limited	64
Murphy Paint Company Limited, The	54
Murray, Alexander, & Company Limited	27 and 62
Nuodex Products of Canada Limited	60
Otis Elevator Company Limited	4
Pedlar People Limited, The	67
Peterboro Lock, The, Manufacturing Co. Limited	46
Pilkington Glass Limited	40
Powers Regulator, The, Co. of Canada, Ltd.	33
Robbins & Myers, The, Co. of Canada Limited	66
Roofers Supply, The, Company Limited	41
Sarco, Canada Limited	3
Sarnia Bridge Co. Limited	60
Simpson, The Robert, Company Limited	62
Smith & Stone Limited	55
Spielman Agencies Limited	68
Standard Tube and T. I. Limited	51
Sternson Structural Specialties Limited	43
Sturgeons Limited	50
Toronto Brick Company Limited	8
Trane Company of Canada Limited	Second Cover
Tremco, The, Manufacturing Co. (Canada) Limited	64
Truscon Steel Company of Canada Limited	63
Unique Sash Balance Company Limited	26
United States Plywoods of Canada Limited	36
Venus Pencil Company Limited	59
Volcano Limited	12
Warden King Limited	24
Wesco Waterpaints (Canada) Limited	56
Westeel Products Limited	13
Wood, G. H., & Company Limited	- Back Cover



M-M SAFETY GRATINGS

on the **BUSIEST CORNER** in Canada


Where traffic is heaviest, safety is most important. That's why M-M Safety Gratings were selected to protect this sidewalk vent at Peel and St. Catherine streets in Montreal.

M-M Safety Gratings assure the safety of pedestrians—let light and air get underground. They are available in fixed, movable, or hinged units—with treads for stairs and fire escapes, and for a wide range of industrial uses. Write for Catalogue TDD-100.

M-M products are manufactured at the Toronto Plant
of Dominion Bridge Company, Limited, 1139 Shaw St.

Plants at: VANCOUVER, CALGARY, WINNIPEG, TORONTO, OTTAWA, MONTREAL.





Gravity Feed Latherizing Soap Systems
... 18.8 stainless steel valves.




Chrome-plated
Lathurn Liquid Soap
Dispenser with
18.8 stainless steel
valves provides a
rich creamy lather.



No. 91 Liquid Soap
Dispenser. Leak-
proof; equipped
with stainless steel
valves.



No. 94 Liquid Soap
Dispenser. Leak-
proof; pump action;
delivers a measur-
ed quantity of soap
as required.



Mop Trucks and Floor Maintenance
Equipment. This Mop Truck
is entirely self-contained; two
22½ gallon tanks.


Specify




Wood's SANITATION EQUIPMENT

- The best equipment for maintaining
buildings in the most modern, sanitary
manner.
- Wood's has 24 branches from coast to
coast and 135 sanitation salesmen.
- May we submit specifications and
quotations?

Floor Scrubbing and
Polishing Machines.
Equipped with full
15" brushes.
C.S.A. approved.




Self-closing,
Fire-proof
Waste Recep-
tacles (with or
without paper
towel dispen-
sers.) Various
types and sizes.



Wood's Registered Deodorizers
will positively re-condition the
air in public toilets and wash-
rooms.

Wood's Electric
Water Cooler.
Automatic
thermostatic
control assures
constant supply
of cool water.



G. H. WOOD & COMPANY LIMITED

MONTREAL

TORONTO

VANCOUVER

Branches throughout Canada